

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: TEICHGRAEBER OIL, INC
Address: 700 N MAIN EUREKA, KS 67045
Phone: (620) 583-7500 Operator License #: 6101
Type of Well: OIL WELL Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 03-14-08 (Date)
by: ALLAN (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
VIOLA Depth to Top: 3585 Bottom: 3594 T.D. 3594

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-131-20-103-00-00
Lease Name: EPPLE "B"
Well Number: 1
Spot Location (QQQQ): 100'E - C S/2 - N/2 - N/2
990' Feet from North / South Section Line
2540' Feet from East / West Section Line
Sec. 3 Twp. 3S S. R. 14 East West
County: NEMAHA
Date Well Completed: 11-04-1985
Plugging Commenced: 03-13-2008
Plugging Completed: 03-14-2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
KINDERHOOK	OIL	GL	278'	8 5/8"	278'	0
HUNTON	OIL	GL	3590'	5 1/2"	3590'	0
MAQUODETA	OIL					
VIOLA	OIL					

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

3-13-08 SPOTTED 20 SKS CEMENT AT 3600' BOTTOM PLUG - 3-14-08 PERFORATED WELL 1350' AND 170' PUMPED 6 SKS GEL SPACER SPOTTED 20 SKS CEMENT AT 1350' PULLED UP TO 350' PUMPED 90 SKS CEMENT TOPPED OFF HOLE CEMENT, CIRCULATED INSIDE AND OUTSIDE 5 1/2" CASING RAN BOND LOG RAN 3-14-08
SHOWED CASING CEMENTED TO SURFACE

RECEIVED
KANSAS CORPORATION COMMISSION

Name of Plugging Contractor: HURRICANE SERVICES, INC WELL SERVICE DIVISION License #: KLN 34059
Address: PO BOX 782228 WICHITA, KS 67278-2228
Name of Party Responsible for Plugging Fees: TEICHGRAEBER OIL, INC
State of KANSAS County, GREENWOOD, ss.

AUG 22 2008
CONSERVATION DIVISION
WICHITA, KS

A C TEICHGRAEBER (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]
(Address) 700 N MAIN EUREKA, KS 67045



SUBSCRIBED and SWORN TO before me this 20th day of August, 2008
[Signature] My Commission Expires: 05-19-2012
Notary Public