


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

NORTH



Locate well correctly on above Section Plat

Sedgwick County. Sec. 8 Twp. 26 Rge. 2 (E) (W)  
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NE SW SE  
Lease Owner John P. Gaty  
Lease Name Phillips Well No. No. 3  
Office Address 6600 E. Central  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed Jan. 11 19.50  
Application for plugging filed Jan. 12 19.50  
Application for plugging approved Jan. 12 19.50  
Plugging commenced Jan. 12 19.50  
Plugging completed Jan. 12 19.50  
Reason for abandonment of well or producing formation Hole full of water

If a producing well is abandoned, date of last production 19...  
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Dwight Lilly  
Producing formation Burgess Sand Depth to top 2958 Bottom 2982 Total Depth of Well 2982 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Burgess Sand	water	2980	2982	7" od	2958	2528

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from... feet to ... feet for each plug set.

Dumped 2 sacks cement at 2982 filled back 2970 mudded hole to 150 ft. set rock bridge to 135 ft. 10 sacks cement on top of rock bridge, mudded hole to cellar. Put 5 sacks cement on top.

NCR  
3-20-08

2-8-50  
1950

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to  
Address

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Max Howell, employee of owner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Max Howell

210 N. Edgemore Dr (Address)

SUBSCRIBED AND SWORN to before me this 16<sup>th</sup> day of January, 1952

Berenice Kooher Notary Public.

My commission expires January 12, 1952 22-5133-8 9-48-10M

PLUGGING  
FILE SEC 8 T 26 R 2 E  
BOOK PAGE 133 LINE 25

WELL LOG - Phillips Well No. 3

OPERATOR: Mr. J. P. Gaty  
c/o Beech Aircraft Corp.  
Wichita, Kansas

Location: NE/4 SW/4 SE/4  
Section 8,  
Township 26 South  
Range 2 East,  
Sedgwick County, Kansas

CONTRACTOR: Morrison Drilling Company, Inc.  
Drawer 712  
El Dorado, Kansas

Production: \_\_\_\_\_

Farm: Phillips Well No. 3

Date Commenced: December 29, 1949

Date Completed: January 6, 1950

Total Depth: 2958 feet.

From	To	Formation	From	To	Formation
110	320	Lime and Shale	2290	2350	Shale & Shells
320	325	Red Rock	2350	2385	Lime & Shale Strks.
325	390	Lime & Shale Brks.	2385	2465	Lime
390	395	Red Rock	2465	2491	Shale & Lime
395	440	Lime & Shale Brks.	2491	2640	Lime
440	675	Lime	2640	2785	Shale & Lime
675	860	Shale & Lime Shells	2785	2832	Lime
860	970	Shale & Lime Strks.	2832	2840	Lime & Shale
970	1055	Shale & Lime Shells	2840	2895	Shale & Lime Strks.
1055	1060	Red Bed	2895	2955	Lime
1060	1085	Shale	2955	2958	Lime & Shale
1085	1090	Red Bed	2958		Total Depth.
1090	1140	Lime & Shale			
1140	1250	Shale			
1250	1330	Lime & Shale			
1330	1470	Shale & Lime Shells			
1470	1515	Lime & Shale			
1515	1615	Shale & Lime Strks.			
1615	1815	Lime & Shale			
1815	1845	Shale			
1845	1900	Lime			
1900	1915	Shale & Shells			
1915	1935	Lime			
1935	2005	Shale & Lime Strks.			
2005	2155	Shale			
2155	2185	Lime			
2185	2245	Shale			
2245	2290	Lime			

Cable Tool Log

2958-64 hard white cemented sand  
 2964-70 Tan Sandy Lime - sand and pyrite  
 2970-78 Burgess Sand  
 2978-79 Blue green dolomite  
 2979-82 Burgess Sand fine  
 HFW @ 2981

I hereby certify that the foregoing is a true and correct copy of the Well Log for the Phillips #3 Well drilled for Mr. J. P. Gaty and completed January 6, 1950.

*C. W. Wilson*  
 C. W. Wilson  
 Secretary-Treasurer

STATE OF KANSAS )


) ss.

COUNTY OF BUTLER )

SUBSCRIBED AND SWORN TO, Before the undersigned, a Notary Public in and for the County and State aforesaid this 18th day of January, 1950.

My Commission Expires January 10, 1951.

*Wm. H. ...*  
 Notary Public



**PLUGGING**  
 FILE SEC 8 T26 D 26  
 COX PAC 133 UN 25

JAN 25 1950