

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Sedgwick SEC. 8 TWP. 26S RGE. 2E E/W
Location as in quarters or footage from lines:
NW/4 SW SW

Lease Owner Wiley R. Ash
 Lease Name Timmerkamp #2 Well No. _____
 Office Address RR #1, Box 114, Rose Hill, Ks. 67133
 Character of Well (Completed as Oil, Gas or Dry Hole): _____
 Date Well Completed _____
 Application for plugging filed _____
 Plugging commenced 3/12/81
 Plugging completed 3/17/81
 Reason for abandonment of well or producing formation _____
Depleted

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Thompson
 Producing formation _____ Depth to top _____ bottom T.D. 3470'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	262'	None
				5-1/2"	3470'	2963'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in and rigged up. Sanded to 3425' and ran 5 sacks cement. Msde shot at 2977'
Pulled a total of 79 joints. Plugged well with 10 sacks gel, 4 sacks hulls and 100
sacks cement 50/50 pos 4% gel. Plugging complete.

RECEIVED
 STATE CORPORATION COMMISSION
3-24-81
MAR 24 1981

(If additional description is necessary, use BACK of this sheet)
 Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
 above-described well, being first duly sworn on oath, says: That I have knowledge of the
 facts, statements, and matters herein contained and the log of the above-described well as
 filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
 (Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of March, 1981

My Commission expires: 

Joan Kelso
 Notary Public.

Petro-Log

Radiation Guard Log

COMPANY WILEY ASH, SR.WELL TIMMERKAMP #2

FIELD _____

COUNTY SEDGWICK STATE KANSASLocation NW/4-SW-SW

Other Services:

Sec. 8 Twp. 26S Rge. 2EPermanent Datum: GROUND LEVEL Elev. 1419
Log Measured From KB, 7 Ft. Above Perm. Datum
Drilling Measured From KELLY BUSHINGElev.: K.B. 1426
D.F. _____
G.L. 1419

Date	6/2/80						
Run No.	ONE						
Depth—Driller	3470						
Depth—Logger	3475						
Btm. Log Inter.	3474						
Top Log Inter.	SURF						
Casing—Driller	8 5/8	@ 262		@	@	@	@
Casing—Logger							
Bit Size	7 7/8						
Type Fluid in Hole	CHEMICAL						
Dens.	10.2	44					
Visc.							
pH	10	113.2ml		ml		ml	ml
Fluid Loss							
Source of Sample	FLOWLINE						
R ₁ @ Meas. Temp.	1.0	@ 90 °F		@ °F	@ °F	@ °F	@ °F
R ₂ @ Meas. Temp.	.75	@ 90 °F		@ °F	@ °F	@ °F	@ °F
R ₃ @ Meas. Temp.	1.5	@ 90 °F		@ °F	@ °F	@ °F	@ °F
Source: R ₁ R ₂ R ₃	CHARTIS						
R ₁ @ BHT	.81	@ 111 °F		@ °F	@ °F	@ °F	@ °F
Time Since Circ.	2 HOURS						
Max. Rec. Temp.	111 °F						
Equip. Location	H-8	GB					
Recorded By	BOB HARRELL AND LEON LEWIS						
Witnessed By	MR. WILEY ASH						