

DRILLING LOG

Company: John P. Gaty
 Farm: Colman No. 1
 Commenced: 3-18-50
 Completed: 4-30-50
 Contractor: Max Howell
 Casings: 10" at 1603'
 8" at 2440'
 7" at 2670'
 5 1/2" at 2982 1/2'

SJ DE NW, Section 32, Twp. 26S,
 R. 2E, Sedgwick County, Kansas
 Cable Tools
 Total Depth - 3,008'

0-3	Collar	942-960	Lime	1810-1815	Shale
-25	Clay	-975	Shale	-1847	Lime
-50	Blue Mud	-993	Lime	-1855	Shale
-110	Shale	-993	Shale	-1865	Lime
-125	Lime	-1010	Lime	-1880	Shale
-155	Shale Shells	-1020	Shale	-1885	Lime
-170	Lime	-1027	Lime	-1890	Shale
-195	Shale	-1035	Shale	-1970	Lime
-200	Lime	-1040	Red Rock	-1980	Shale
-210	Shale	-1055	Shale	-2020	Lime
-230	Lime	-1060	Lime	-2050	Shale
-250	Shale	-1065	Red Rock	-2105	Shale & Shells
-260	Lime	-1075	Lime	-2160	Shale
-265	Shale	-1085	Shale, Brown	-2210	Lime
-280	Lime	-1090	Lime	-2215	Shale
-305	Shale	-1100	Shale	-2220	Lime
-312	Red Rock	-1115	Lime Broken	-2230	Shale
-335	Shale	-1125	Shale	-2295	Lime
-350	Lime	-1145	Lime	-2303	Lime, Soft
-380	Shale	-1197	Shale	-2340	Lime, White
-420	Lime	-1203	Lime	-2355	Lime, Sandy
-430	Shale	-1225	Shale	-2360	Lime, Hard
-475	Lime	-1228	Lime	-2423	Lime
-515	Lime, Brown	-1230	Shale	-2430	Shale
-517	Shale	-1241	Shale, Blk.	-2433	Lime
-530	Lime	-1265	Shale	-2443	Shale
-540	Shale	-1297	Lime	-2448	Lime, Hard and Sharp
-565	Lime	-1303	Shale	-2460	Shale, Light
-560	Shale	-1335	Lime	-2480	Shale
-600	Lime	-1340	Shale	-2520	Shale, Sandy
-605	Shale	-1355	Lime	-2664	Lime, K. C.
-620	Lime	-1365	Shale	-2670	Shale
-625	Red Rock	-1377	Lime	-2700	Lime
-645	Lime	-1395	Shale	-2730	Shale, Dark
-655	Shale	-1410	Lime	-2834	Shale & Shells
-660	Lime	-1430	Shale	-2860	Lime
-665	Shale	-1525	Lime	-2865	Shale
-670	Lime	-1555	Shale	-2875	Lime
-680	Shale	-1575	Lime	-2881	Shale
-685	Lime	-1580	Shale	-2900	Lime
-700	Shale	-1600	Lime	-2947	Shale & Shells
-705	Red Rock	-1610	Shale	-2955	Lime
-715	Lime	-1638	Lime	-2959	Shale
-735	Shale	-1645	Shale, Brown	-2982 1/2	Top V. C. Shale
-745	Lime	-1652	Lime	-2984 1/2	Sand and Shale
-750	Shale	-1660	Shale	-3003	Sand
-768	Lime	-1664	Lime		
-780	Shale	-1675	Shale, Blk.		
-815	Lime	-1680	Lime		
-825	Shale	-1685	Shale		
-840	Lime	-1710	Lime		
-845	Shale	-1720	Shale		
-852	Red Rock	-1730	Lime		
-860	Lime	-1735	Shale		
-880	Shale	-1745	Lime		
-890	Lime	-1760	Shale		
-900	Shale	-1795	Lime		
-937	Lime	-1800	Shale		
-942	Shale, Blk.	-1810	Lime		

Water Record

1 1/2 Bailer at 052-060
 1 Bailer at 1903
 Hole Full Water at 2295-2300
 Hole Full Water at 2394-2600
 1 Bailer at 2994

