

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

147-20208-00-00

Lease Operator: JOHNSON OIL  
Address: 258 east highway 36 phillipsburg kansas  
Phone: (785) 543-6171 Operator License #: 3077  
Type of Well: oil Docket #: \_\_\_\_\_  
*(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)*  
The plugging proposal was approved on: march 12 2008 (Date)  
by: herb denis (KCC District Agent's Name)  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (if needed attach another sheet)  
3150 Depth to Top: \_\_\_\_\_ Bottom: 3378 T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - DEC 10 1975  
Lease Name: WEINMAN B  
Well Number: 1  
Spot Location (QQQQ): SW - NE - NW  
990 Feet from  North /  South Section Line  
1650 Feet from  East /  West Section Line  
Sec. 25 Twp. 2 S. R. 19  East  West  
County: PHILLIPS  
Date Well Completed: Dec 10 1975  
Plugging Commenced: mar 13 2008  
Plugging Completed: mar 13 2008

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
lansing k/c	oil	3150	3378	4 1/2	3550	0
surface		0	200	8 5/8	200	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.


PAT BEDORE showed up representing the state of kansas .He then instructed us to run our tubing to 2000 feet. We then instructed allied cementing to start pumping cement until it circulated with 100 sacks cement and 300lbs of hals . We then pulled pipe, tied onto suface casing and pumped 20 sacks 400lbs. After that we tied onto production 4 1/2 casing pumped 235 sacks cement shut in at 50 psi. plugging completed.

Name of Plugging Contractor: allied cementing License #: n/a 99996 RECEIVED  
Address: Russell kansas KANSAS CORPORATION COMMISSION  
AUG 29 2008  
Name of Party Responsible for Plugging Fees: KEVIN JOHNSON CONSERVATION DIVISION  
State of KANSAS County, PHILLIPS, ss. WICHITA, KS

(Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) [Signature]  
(Address) 258 East Highway 36 Phillipsburg

SUBSCRIBED and SWORN TO before me this 26<sup>th</sup> day of August, 2008  
Waneta Fae Gower My Commission Expires: 12-05-2011  
Notary Public




Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

PKT



24 S. Lincoln Street  
P.O. Box 31  
Russell, KS 67665-2906

Voice: (785) 483-3887  
Fax: (785) 483-5566



# INVOICE

Invoice Number: 112862  
Invoice Date: Mar 13, 2008  
Page: 1

<b>Bill To:</b>
Johnson Oil 258 Hwy 36 Phillipsburg, KS 67661

Customer ID	Well Name/# or Customer P.O.	Payment Terms	
John	Weiman B #1	Net 30 Days	
Job Location	Camp Location	Service Date	Due Date
KS	Russell	Mar 13, 2008	4/12/08

Quantity	Item	Description	Unit Price	Amount
255.00	MAT	Class A Common	12.15	3,098.25
170.00	MAT	Pozmix	6.80	1,156.00
17.00	MAT	Gel	18.25	310.25
8.00	MAT	Cottonseed Hulls	27.95	223.60
450.00	SER	Handling	2.05	922.50
90.00	SER	Mileage 450 sx @.09 per sk per mi	40.50	3,645.00
1.00	SER	Old Hole Plug	1,045.00	1,045.00
90.00	SER	Mileage Pump Truck	7.00	630.00

*CA # 2397  
Margaret  
3-25-08*

RECEIVED  
KANSAS CORPORATION COMMISSION  
**AUG 29 2008**  
CONSERVATION DIVISION  
WICHITA, KS

ALL PRICES ARE NET, PAYABLE  
30 DAYS FOLLOWING DATE OF  
INVOICE. 1 1/2% CHARGED  
THEREAFTER. IF ACCOUNT IS  
CURRENT, TAKE DISCOUNT OF

Subtotal	11,030.60
Sales Tax	639.77
Total Invoice Amount	11,670.37
Payment/Credit Applied	
<b>TOTAL</b>	<b>11,670.37</b>

\$1103.06

# ALLIED CEMENTING CO., LLC.

30303

TO P.O. BOX 31  
RUSSELL, KANSAS 67665

SERVICE POINT:

Russell

DATE <u>3-12-08</u>	SEC. <u>25</u>	TWP. <u>2</u>	RANGE <u>19</u>	CALLED OUT	ON LOCATION	JOB START	JOB FINISH <u>2:45 p.m.</u>
LEASE <u>weimar</u>	WELL # <u>B#1</u>	LOCATION <u>Speed N to Hwy 36</u>			COUNTY <u>Phillips</u>	STATE <u>KS</u>	
<input checked="" type="radio"/> OLD OR NEW (Circle one)			<u>5 N 3/4 E Sinto</u>				

CONTRACTOR Co Tools  
 TYPE OF JOB Old Hole Plug  
 HOLE SIZE \_\_\_\_\_ T.D. \_\_\_\_\_  
 CASING SIZE 4 1/2 \_\_\_\_\_ DEPTH \_\_\_\_\_  
 TUBING SIZE 2 3/8 \_\_\_\_\_ DEPTH 2016  
 DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_  
 PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_  
 MEAS. LINE \_\_\_\_\_ SHOE JOINT \_\_\_\_\_  
 CEMENT LEFT IN CSG. \_\_\_\_\_  
 PERFS. \_\_\_\_\_  
 DISPLACEMENT \_\_\_\_\_

OWNER \_\_\_\_\_  
 CEMENT Used all Cement  
 AMOUNT ORDERED 425 @ 60 49.60  
800 #hubs Used 500 #hubs

COMMON	<u>255</u>	@	<u>12.15</u>	<u>3,098.25</u>
POZMIX	<u>170</u>	@	<u>6.80</u>	<u>1,156.00</u>
GEL	<u>17</u>	@	<u>18.25</u>	<u>310.25</u>
CHLORIDE		@		
ASC		@		
<u>Hubs</u>	<u>8</u>	@	<u>27.95</u>	<u>223.60</u>

EQUIPMENT

PUMP TRUCK CEMENTER Shane  
 # 366 HELPER Matt  
 BULK TRUCK  
 # 396 DRIVER Rocky  
 BULK TRUCK  
 # \_\_\_\_\_ DRIVER \_\_\_\_\_

<b>RECEIVED</b>				
KANSAS CORPORATION COMMISSION				
<b>AUG 29 2008</b>				
CONSERVATION DIVISION				
HANDLING	<u>4 MILES</u>	@	<u>2.05</u>	<u>922.00</u>
MILEAGE	<u>109.68</u>	@		<u>3,645.00</u>
TOTAL				<u>9,365.00</u>

REMARKS:  
2016' Mixed 100skt with 300 #hubs  
pulled tubin to 1000' to Circulate  
Cement Used 70 skt 200 #hubs  
Came out of hole put 4 1/2 size  
on mixed 20skt + shut-in @ 400psi  
Tied on to Backside mixed 235 skt  
+ shut-in @ 50 psi,

SERVICE

DEPTH OF JOB				
PUMP TRUCK CHARGE			<u>1,045.00</u>	
EXTRA FOOTAGE		@		
MILEAGE	<u>90 mi</u>	@	<u>7.00</u>	<u>630.00</u>
MANIFOLD		@		
		@		
		@		
TOTAL				<u>1,675.00</u>

CHARGE TO: Johnson Oil  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

PLUG & FLOAT EQUIPMENT