

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-015-20,096-A 00-01

LEASE NAME Cunningham

WELL NUMBER #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

2970 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 5 TWP. 26 RGE. 3 (E) or (W)

COUNTY Butler

Date Well Completed 8-28-88

Plugging Commenced 8-28-88

Plugging Completed 8-28-88

LEASE OPERATOR Lee Phillips

ADDRESS 125 N. Market Suite 1532 Wichita, Ks.

PHONE# (316) 264-6392 OPERATORS LICENSE NO. 5215

Character of Well D & A

(Oil, Gas, (D&A) SWD, Input, Water Supply Well)

The plugging proposal was approved on 8-28-88 (date)

by Don Thompson, Eldorado, Ks. (KCC District Agent's Name).

Is ACO-1 filled? no If not, is well log attached? yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3285'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0	208	8 5/8	Cemented	to surface

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Mixed 35 sx and pumped to T.D. of 3285'. Filled hole with 60 vis. rotary mud to 250'. Mixed 35 sx and pumped down pipe to 250'. Filled hole to 60'. Mixed 25 sx and filled hole to ground level. Put 10 sx in rat hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Berentz Drilling Co., Inc. License No. STATE 5882

Address 115 W. Third P. O. Box 428 Eureka, Ks. 67045

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Lee Phillips

STATE OF Kansas COUNTY OF Greenwood, ss.

Kevin F. Hough (Employee of Operator or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 115 W. Third Eureka, KS.

SUBSCRIBED AND SWORN TO before me this 6th day of September, 19 88

Mary Alice Evenson
Notary Public

My Commission Expires: 9-1-88

RECEIVED
STATE CORPORATION COMMISSION
SEP - 7 1988
9-7-88
CONSERVATION DIVISION
Wichita, Kansas

MARY ALICE EVENSON
State of Kansas
My Appt. Exp. Sept. 1, 1989

L O G O F W E L L

Cunningham #1
2970' FSL 4290' FEL
Section 5-26-3E
Butler County, Kansas

OPERATOR: Lee Phillips Oil Company

CONTRACTOR: Berentz Drilling Company, Inc.

Commenced with Rotary: 8-23-88

Completed with Rotary: 8-28-88

Casing: 8 5/8"-----208' cemented with 135'sx

Washdown to old T.D. 2813'

OLD TOPS

2318-2483'	Lime Kansas City
2776'	Lime & Shale
3071'	Lime Mississippi
3126'	Shale Kinderhook
3175'	Lime Hunton
3187'	Lime Viola
3260'	Sand Simpson
3285	Lime Arbuckle R.T.D.

RECEIVED
STATE CORPORATION COMMISSION

SEP - 7 1988

CONSERVATION DIVISION
Wichita, Kansas