

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

STATE OF KANSAS STATE CORPORATION COMMISSION

Give All Information Completely Make Required Affidavit Mail or Deliver Report to: Conservation Division State Corporation Commission 800 Bitting Building Wichita, Kansas

Butler County. Sec. 5 Twp. 26 Rge. 3 (E) E (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. NE SE SE

Lease Owner K. T. Wiedemann

Lease Name Ethel Wait Well No. 2

Office Address 1515 W. Sixth, El Dorado, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry

Date well completed July 23, 1957 19

Application for plugging filed Sept. 1, 1957 19

Application for plugging approved " 19


Plugging commenced " 19

Plugging completed Sept. 3, 1957 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eugene Graham

Producing formation Depth to top Bottom Total Depth of Well 2825 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Table with 7 columns: Formation, Content, From, To, Size, Put In, Pulled Out. Contains data for casing sizes 10 3/4 and 7, and depths 105, 2825, 2670.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Dumped 25ft of gravel in hole at 2795' fillup to 2770

Dumped 10 sx of cement on top of gravel Heavy mud to 200'

Set plug @ 200'

Rock Bridge to 185'

15 sx cement on top of bridge

Mud to 30'

10 sx cement to surface

35 sx cement to plug hole

RECEIVED STATE CORPORATION COMMISSION 9-6-57 SEP 6 1957 CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Beaumont Petroleum Company

Address Box 285, El Dorado, Kansas

STATE OF KANSAS, COUNTY OF BUTLER, SS.

M. W. Collins (employee of owner) or (owner or operator) of the above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) M. W. Collins

El Dorado, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 4 day of September, 1957.

Roberta Cottle

Notary Public.

My commission expires 3-21-60

PLUGGING FILE SEC 5 T 26 R 3 E BOOK PAGE 41 LINE 16

BEAUMONT PETROLEUM COMPANY

#2 Ethel Wait

Rot. TD 2825
 Comm. Rot. 7-2-57
 Comp. Rot. 7-10-57
 Cable Tool TD 2794½
 Comm. C.T. 7-16-57
 Comp. C.T. 7-23-57

Cemented
 10 3/4 Surface w/160sx
 7" Oil String w/30 sx
 Liberty OWC Co.

NE SE SE
 Sec. 5-26-3e
 Butler Co.

Casing Record

10 3/4 105'
 7" 20# 2825' used smiss csg. Recovered 2670'

FIGURES INDICATE BOTTOM OF FORMATIONS
 ROTARY BUSHING 5'6" ABOVE GROUND LEVEL

cellar	5
clay	35
lime-shale brks	215
lime	560
shale-lime strks	1000
shale	1070
lime-shale brks	1260
lime-shale	1465
lime	1770
shale-lime strks	2005
lime	2140
shale-lime strks	2300
shale	2305
lime	2470
shale	2545
lime	2550
lime-shale	2773
Miss. lime	2825 Rot. TD
Cable Tool	
lime	2794½ Effective TD

September 3, 1957
 Plugged & Abandoned

PLUGGING
 FILE SEC 5 T. 26 R 3E
 BOOK PAGE 41 LINE 16