


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Butler County, Sec. 5 Twp. 26 Rge. 3 (E) E (W)

Location as "NE/CNW/SW" or footage from lines SE SE SE
Lease Owner K. T. Wiedemann
Lease Name Ethel Wait Well No. 1
Office Address 127 1/2 W. Central, El Dorado, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Producer
Date well completed 4-30-50 19
Application for plugging filed 2-23-54 19
Application for plugging approved 2-23-54 19
Plugging commenced 2-28-54 19
Plugging completed 2-28-54 19
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Flat

If a producing well is abandoned, date of last production June 1953
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Lawrence Mathews, Jr.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2767 1/2 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	80'	
				5 1/2	2753'	2200'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set 3 sx cement at 2767 1/2
Heavy mud from 2767 1/2 to 200'
Set Rock Bridge from 200' to 185'
Heavy mud to surface
Set 5 sx cement at surface


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Beaumont Petroleum Co. - company tools
Address El Dorado, Kansas

STATE OF KANSAS, COUNTY OF BUTLER, ss.
Carl Hankenson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Carl Hankenson

SUBSCRIBED AND SWORN TO before me this 25th day of March, 1954

My commission expires 12-5-55



(Address) New Orleans
Notary Public.

PLUGGING
FILE SEC J T 26 R 3E
BOOK PAGE 16 LINE 10

REC
STATE OF KANSAS
CORP
3-26-54

ETHEL WAIT #1

Rotary T.D. 2755
 Comm. Rot. 4-6-50
 Comp. Rot. 4-15-50
 Franks Rotary

SE SE SE
 Sec. 5-26-3E
 Butler County

Cable Tools T.D. 2767½
 Comm. C.T. 4-26-50
 Comp. R.T. 4-30-50 &
 11-8-50

Elev: 1314.5

Casing Record

8 5/8 Surface 80'
 5 1/2 Oil String 2753' Recovered 2200'

FIGURES INDICATE BOTTOM OF FORMATION
 ROTARY BUSHING 3'6 FROM GROUND LEVEL

cement	80	
lime-shale brks	460	
shale-shells	700	
lime	746	
shale-lime strks	800	
lime-shale brks	835	
shale-shells	993	
lime	1030	
shale-shells	1060	
lime	1087	
shale-lime	1125	
lime	1180	
shale	1234	
lime-shale brks	1290	
shale	1437	
lime	1610	
lime-shale	1640	
lime	1725	
shale-shells	1740	
sandy shale	1753	
lime	1772	
lime-shale	1790	
shale	1927	
lime	2005	
lime-shale brks	2110	
lime	2155	
shale-shells	2195	
shale-lime	2275	
shale	2289	
lime	2454	
shale	2505	
shale-shells	2725	
cherty congl.	2736	
congl. shale	2745	
lime - cherty	2755	Rot. T.D.
lime	2767½	Cable Tool T.D.

2-28-54
 Plugged & Abandoned

PLUGGING
 FILE SEC 5 T 26 R 3E
 BOOK PAGE 16 LINE 10

MAILED 26 1954
 CONSERVATION DIVISION
 Wichita, Kansas