


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Butler County. Sec. 5 Twp 26 Rge. 3 (E) E (W)
Location as "NE/CNW%SW%" or footage from lines NE NE NE
Lease Owner K. T. Wiedemann
Lease Name Phares Heirs Well No. 1
Office Address 1515 W. Sixth, El Dorado, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed June 3, 19 57
Application for plugging filed November 17, 19 59
Application for plugging approved " 19
Plugging commenced " 19
Plugging completed " 20, 19 59
Reason for abandonment of well or producing formation Flood all water

If a producing well is abandoned, date of last production October 19 59
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Lee Guthrie
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2843 Feet
Show depth and thickness of all water, oil and gas formations. 2843

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10 3/4	75	
				7"	2843	2566

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole w/rock from 2843 to 2750
Dumped 5 sacks cement on top rock
Heavy mud to 220 w/15' rock bridge
Dumped 60 sacks cement on rock bridge
Mud to 35'
Rock bridge from 35' to 30'
Dumped 15 sacks cement to surface

RECEIVED
STATE CORPORATION COMMISSION
NOV 30 1959
11-30-59
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Beaumont Petroleum Company
Address 1515 W. Sixth, El Dorado, Kansas


STATE OF KANSAS, COUNTY OF BUTLER, ss.
C. D. Dunbar (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
El Dorado, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 23 day of November, 19 59

My commission expires 3-21-60

[Signature]
Notary Public.



R

BEAUMONT PETROLEUM COMPANY

#1 Phares Heirs

Rot. T.D. 2843
Comm. Rot. 5-27-57
Comp. Rot. 6-3-57

NE NE NE
Sec. 5-26-3e
Butler County, Ks.

Cable Tool TD 2829 Eff.
Comm. C.T. 6-8-57
Comp. C.T. 6-11-57

Cemented
10 3/4 " Surface w/75 sx
7" Oil String w/40 sx
Liberty OWC Co.

Casing Record

10 3/4 75'
7" 2843' 20# Smls Csg.

FIGURES INDICATE BOTTOM OF FORMATIONS
ROTARY BUSHING 5' ABOVE GROUND LEVEL

shale	40	
shale-lime	65	
lime	110	
lime-shale brks	440	
lime	630	
shale	1030	
lime-shale brks	1800	
shale-shells	1955	
shale-lime	2120	
lime	2200	
lime-shale	2260	
shale-lime	2305	
lime	2470	
shale-lime	2640	
lime	2691	
shale	2756	
lime	2843	Rot. T.D.
Cable Tool		
lime	2829	Eff. T.D.

STATE OF KANSAS
NOV 30 1959

November 20, 1959
Plugged & Abandoned