

2-040824

KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2125
Wichita, KS 67202

1-9

API NUMBER: 15-015-23,457-00-00

NW NE NE SECTION 1 TOWNSHIP 26 RANGE 3E
4950 FEET FROM S SECTION LINE
990 FEET FROM E SECTION LINE

OPERATOR LICENSE #5892
OPERATOR Berentz Drilling Co., Inc.
NAME & PO Box 782228
ADDRESS Wichita, KS 67278

LEASE NAME: McNeal #1
COUNTY: Butler
WELL TOTAL DEPTH: 3012' 97.89
CONDUCTOR PIPE: " @ "
SURFACE CASING: 8 5/8" @ 215'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A
OTHER WELL AS HEREINAFTER INDICATED:

PLUGGING CONTRACTOR: Berentz Drilling Co., Inc.
ADDRESS: PO Box 782228, Wichita, KS 67278 LICENSE: #

COMPANY TO PLUG AT: HOUR: DAY: MONTH: YEAR: 1996

PLUGGING PROPOSAL RECEIVED FROM: Tim Berentz

COMPANY NAME: Berentz Drilling Co., Inc. PHONE:

WERE: 35 sacks at 3000' 35 sacks at 265' 25 sacks at 60' 10 sacks
rat hole

PLUGGING PROPOSAL RECEIVED BY:
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { } PART { } NONE { }

COMPLETED: HOUR: 2145 DAY: 9 MONTH: 1 YEAR: 1996


ACTUAL PLUGGING REPORT: Drilling pipe was run open end to 3000' where 35
sacks cement was spotted. The Drilling pipe was pulled to 265' where 35
sacks cement was spotted. The Drilling pipe pulled to 60' where 25
sacks of cement circulated cement to surface. The rat hole was
circulated with 10 sacks of cement.

KANSAS CORPORATION COMMISSION

REMARKS: Sun Cement 005037 50/50 Poz 2% Gel

I DID NOT OBSERVE THIS PLUGGING.

MAR 05 1996
3-5-96
CONSERVATION DIVISION
WICHITA, KS


Steve Van Gieson (AGENT)

INVOICED
DATE MAR 05 1996
INV. NO. 44930