

2 030581

3-30-88

015-20,194-00-00

API NUMBER 15-

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE NW NW, SEC. 2, T 26 S, R 3 XX W/E

4950 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3710

Lease Name Kiowa Lands Well # 1 A

Operator: Midco Energy, Inc.

County Butler 88.08

Name & Address P.O. Box 781025

Well Total Depth 2710 feet

Wichita, KS 67278

CONDUIT Pipe: Size 4 1/2" feet 2701

Surface Casing: Size 8 5/8 feet 190

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Jonathan Oil Company License Number 4231

Address 804 N. Haverhill Rd., Eldorado, KS 67042

Company to plug at: Hour: 10:00am Day: 28 Month: 3 Year: 19 88

Plugging proposal received from Lynn Butler

(company name) Jonathan Oil Company (phone)

were: Rock 50' above open hole, 4 sxs cement. Shoot and pull casing. Set top bridge @270', fill with redimix to surface.

Plugging Proposal Received by District #2 Office (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 11:00 Day: 30 Month: 3 Year: 1988

ACTUAL PLUGGING REPORT Filled hole with fine gravel to 2650', dumped 4 sxs cement w/bailer. Shot and pulled 2260' of 4 1/2" casing. Bailed hole to 270', set rock bridge @260'-240. Lewis & West Redimix #09473 dumped 2 yards redimix sand and cement to surface.

RECEIVED  
STATE CORPORATION COMMISSION  
4-11-88  
APR 11 1988

Remarks: CONSERVATION DIVISION Wichita, Kansas (Additional description is necessary, use BACK of this form.)

(did not) observe this plugging.

DATE 4-13-88

Signed Don Thompson (TECHNICIAN)

INV. NO. 20364

3-30 AUG 9 1988 SEP 13 1988