

2 100435

11-30

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 015-23,102-00-00

SW, SEC. 2, T 26 S, R 3 W/E

3530 feet from S section line

1500 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5120

Lease Name Foulston Well # A-2

Operator: Range Oil Co., Inc.

County Butler 88.08

Name & Address 1120 KSBT Bldg

Well Total Depth 2710 feet

125 N. Market

Conductor Pipe: Size 4-1/2" feet 2704'/125 SX

Wichita, KS 67202

Surface Casing: Size 8-5/8" feet 220'/165 SX

316-265-6231

Abandoned Oil Well Gas Well Input Well SWD Well O&A

Other well as hereinafter indicated open hole

Plugging Contractor Jonathan Oil Co License Number 4231

Address P. O. Box 1098, El Dorado, KS 67042

Company to plug at: Hour: 1:00 Day: 30 Month: 11 Year: 19 88

Plugging proposal received from John Brickley

(company name) Jonathan Oil Co. (phone) 316-321-4435

were: Sand to 2650' - 5 sx - shoot & pull pipe - bridge at 300' to 275' -
redi mix to surface.

Plugging Proposal Received by Sanders
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 1:45 Day: 30 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT Sanded to 2694' and dumped w/bailer 6 sx of cement - shot
& pulled approx. 1214' of 4-1/2" - set bridge rock/wood from 300' to 270' and
filled to surface with 4-3/4 yds redimix slurry 10% sand.

RECEIVED
STATE CORPORATION COMMISSION

DEC 8 1988

12-8-88
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Slurry mix 10% sand - Lewis & West Cement #12677
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE DEC 9 1988

INV. NO. 23294

WC

Signed Johnny Sanders
(TECHNICIAN)