

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-21222-00-00
Spot: S2SESW Sec/Twnshp/Rge: 1-26S-3E
200 feet from S Section Line, 660 feet from E Section Line
Lease/Unit Name: JACOBS Well Number: 1
County: BUTLER Total Vertical Depth: 2755 feet

Operator License No.: 31528
Op Name: KELSO, MIKE - OIL, INC.
Address: PO BOX 467
CHASE, KS 67524

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 180 125 SX CMT
Production: Size 4.5 feet: 2700 **\$ 89.54**
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 04/20/2001 12:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MIKE KELSO Company: SAME Phone: (620) 938-2943

Proposed Plugging Method:

See actual report.

Plugging Proposal Received By: DONALD HOBERECHT

WitnessType: Plugging Operations Partially Witnessed

Date/Time Plugging Completed: 04/20/2001 12:00 PM

KCC Agent: DONALD HOBERECHT

Actual Plugging Report:

Sand back to 2660' w/4sxs cement on top of sand. Shoot and pull casing to 250'. Circulate cement from 250' to surface w/115sxs 60/40 poz 4%gel.

INVOICED

DATE 5-02-01

INV. NO. 2001061755

RECEIVED
KCC DISTRICT #2

APR 27 2001

4-27-01


WICHITA, KS

Remarks: UNITED # 2444

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)