

7-31

2-050717

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-015-21,397-00-00

SW SE SE, SECTION 3 TOWNSHIP 26 RANGE 3E

OPERATOR LICENSE # 4336 330 FEET FROM S SECTION LINE

OPERATOR GOBEN'S UNITED PETROLEUM INC 1000 FEET FROM E SECTION LINE

NAME & 3223 ENGLISH

ADDRESS WICHITA, KS 67218

LEASE NAME: PARSLEY #2A

COUNTY: BUTLER 90.19

WELL TOTAL DEPTH: 2775'

PIPE: 4 1/2" @ 2774'

SURFACE CASING: 8 5/8" @ 200'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: SAGE OIL COMPANY

ADDRESS: BOX 12, VIRGIL, KS 66870 LICENSE: 5684

COMPANY TO PLUG AT: HOUR: 13:30 DAY: 31 MONTH: 7 YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: DISTRICT II

COMPANY NAME: SAGE OIL COMPANY PHONE: (316) 678-3440

WERE: SAND BACK AND SPOT 4 SACKS OF CEMENT AT 2675'. SHOOT 4 1/2" CASING AT 1500' AND PULL UP TO 260'. CIRCULATE CEMENT FROM 260' TO SURFACE. PULL CASING OUT OF HOLE AND TOP OFF WITH CEMENT.

PLUGGING PROPOSAL RECEIVED BY: GEORGE SAGE

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 17:00 DAY: 31 MONTH: 7 YEAR: 1997

ACTUAL PLUGGING REPORT: SANDED BACK AND SPOTTED 4 SACKS OF CEMENT AT 2675'. SHOT 4 1/2" CASING AT 1484' AND PULLED UP TO 260'. CIRCULATED CEMENT FROM 260' TO SURFACE. PULLED CASING OUT OF HOLE AND TOPPED OFF WITH CEMENT.

REMARKS: 90 SACK CEMENT


INVOICED
RECEIVED
KANSAS CORPORATION COMMISSION

DATE 10-3-97 OCT 03 1997
49204 10-3-97

INV. NO. 49204 CONSERVATION DIVISION
WICHITA, KS

7-31 OCT 31 1997

I DID OBSERVE THIS PLUGGING.


JERRY CLARK