

7-5-88 15-06-00767-00-00

2 030660

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1-12-1949

NW SE SE, SEC. 3, T 26 S, R 3 XWE
990' feet from S section line
990' feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9982

Lease Name Parsley Well # 1

Operator: James A. Cook

County Butler 87.95

Name & Address P.O. Box 575

Well Total Depth 2706' feet

Augusta, KS 67010

Conductor Pipe: Size 5 1/2" feet 2697' / 35sx

Surface Casing: Size 7" feet 126'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor United Cementing Co. License Number

Address 2510 West Sixth; Eldorado, KS 67042

Company to plug at: Hour: 11:00 Day: 29 Month: 6 Year: 19 88

Plugging proposal received from James Cook

(company name) James A. Cook (phone) 316-775-6178

work: Spot cement on bottom, test casing, perf. casing. 300', pump cement to surface.

Plugging Proposal Received by District #2 Office
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:00 Day: 5 Month: 7 Year: 19 88

ACTUAL PLUGGING REPORT Ran 2 3/8" tub to 2665' United #2487 spotted 35 sx 60/40

Posmix 2% gel, top cement. 2304'. Perf. casing 270' United #2506 pumped 270 sx 60/40

Posmix 6% total gel to surface. Cement fell down hole. Ran 1" outside 7" to 120'

United #2511 pumped 105 sx 60/40 Posmix 6% total gel to surface, filled 5 1/2" csg., pulled 1#.

RECEIVED
STATE CORPORATION COMMISSION
STATE CORPORATION DIVISION
7-19-88
JUL 19 1988

Remarks: (If additional description is necessary, use BACK of this form.) CONSERVATION DIVISION
Wichita, Kansas

INVOICED
I did not observe this plugging.

DATE 7-21-88

Signed Don Thompson
(TECHNICIAN)

INV. NO. 24572