

6-26

198 R

2-100595

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

RECEIVED
7-17-90
JUL 17 1990
CONSERVATION DIVISION
Wichita, Kansas

API NUMBER: 15-015-21,196-00-00
SW , SECTION 3 TOWNSHIP 26 RANGE 3E

OPERATOR LICENSE # 4336 FEET FROM S SECTION LINE
FEET FROM E SECTION LINE

OPERATOR Goben's United Petroleum
NAME & 1333 N. Broadway
ADDRESS Wichita, KS 67214

LEASE NAME: Wait #2
COUNTY: Butler / 90.06

WELL TOTAL DEPTH: 2771'
CONDUCTOR PIPE: 4-1/2" @ 2771' / 75 sx

SURFACE CASING: 8-5/8" @ 201' / 100 sx

ABANDONED OIL WELL GAS WELL INPUT WELL SHD D&A

OTHER WELL AS HEREINAFTER INDICATED: Perf 2751-53'

PLUGGING CONTRACTOR: Bill McPherson
ADDRESS: Box 168, Augusta, KS 67010 LICENSE: 5495

COMPANY TO PLUG AT: HOUR: 12:00p DAY: 26 MONTH: 6 YR: 1990

PLUGGING PROPOSAL RECEIVED FROM: Bill McPherson
COMPANY NAME: McPherson Drilling PHONE: 316-775-3078

WERE: Sand 50' above top perf & dump 5 sx cmt - shoot & pull pipe - pump from top, 1 hull, 2 gel, 100 sx cmt.

PLUGGING PROPOSAL RECEIVED BY: Don Thompson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 1:00p DAY: 26 MONTH: 6 YEAR: 1990

ACTUAL PLUGGING REPORT:

Ran wireline plug to 2700' - sanded top 50' & dumped 4 sx cmt - shot & pulled pipe - welded swedge on surface - pumped thru swedge 1 sx hull, 2 sx gel & 100 sx cmt. United #699 60/40 2%

REMARKS: Oper #600# Shut in 250#

I DID OBSERVE THIS PLUGGING.

John Sanders
John Sanders (AGENT)

INVOICED

DATE 7-26-90

INV. NO. 28745

MP

6-26

AUG 20 1990 OCT 17 1990