

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

6-20

2-010076

API NUMBER: 15-015-21,399-00-00

NE SE SE, SECTION 4 TOWNSHIP 26 RANGE 3E

OPERATOR LICENSE # 4336 990 FEET FROM S SECTION LINE
330 FEET FROM E SECTION LINE

OPERATOR GOBEN'S UNITED PETROLEUM INC
NAME & 3223 ENGLISH
ADDRESS WICHITA KS 67218

LEASE NAME: DOTY #1 90.35
COUNTY: BUTLER
WELL TOTAL DEPTH: 2780'

PIPE: _____

SURFACE CASING: 8-5/8" @ 200'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SLD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: W W DRILLING COMPANY

ADDRESS: RR3, BOX 66, ELDORADO KS 67042 LICENSE: 6012

COMPANY TO PLUG AT: HOUR: 10:00 DAY: 20 MONTH: 6 YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: LEON BEAN

COMPANY NAME: UNITED CEMENTING & ACID CO INC PHONE: 316-

WERE: GRAVEL TO 2700' & TOP W/4 SX CMT - SHOOT PIPE OFF &
PULL SAME - BUILD BDRIDGE @ 250' - RUN 1" TUB TO 250' &
CIRCULATE CMT TO THE SURFACE.
4-1/2" CSG @ 2780'
PERFS @ 2748' TO 2749'

PLUGGING PROPOSAL RECEIVED BY: MIKE WILSON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (X) NONE (_____)

COMPLETED: HOUR: 12:00 DAY: 20 MONTH: 6 YEAR: 1995

ACTUAL PLUGGING REPORT:

GRAVELED TO 2700' & TOPPED W/4 SX CMT - SHOT PIPE OFF
@ 1449' & PULLED SAME - BUILT BRIDGE @ 280' - RAN 1"
TUB TO 273' & CIRC 112 SX CMT TO SURF
RETRIEVED 1449' OF 4-1/2" CSG

REMARKS: USED 60/40 POZ W/3% GEL BY UNITED #2002

RECEIVED
KANSAS CORPORATION COMMISSION

I DID OBSERVE THIS PLUGGING.

JUN 29 1995

INVOICED

Michael R. Wilson
Michael R. Wilson (AGENT)

6-29-95
CONSERVATION DIVISION
FORM GR 2/83
REV. 3/90

DATE 6-30-95
INV. NO. 43032