

2 030264

Comp. 9-19-1967

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

NENE NW, SEC. 4, T 26 S, R 3 E

4290' feet from N/S section line

2910' feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6420

Lease Name Zurechen Well # B-1

Operator: K.R.M. Petroleum Corp.

County Butler 89.87

Name & Address 1900 Grant St. #300

Well Total Depth 2765' feet

Denver, Co. 80203

~~Surface~~ Pipe: Size 4 1/2" feet 2763'

Surface Casing: Size 8 5/8" feet 200'

Abandoned Oil Well Gas Well Input Well SMD Well D&A

Other well as hereinafter indicated oil well connected to S.W.D.

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, Kv. 64524

Company to plug at: Hour: 08:30 Day: 11 Month: 7 Year: 19 85

Plugging proposal received from Mike Gomez

(company name) Kelso Casing Pulling (phone) _____

were: Perf. 2712' to 2765' fiberglass tub and packer left in hole.
top of tub. 853'. run tub to 850' spot 50 sep. cent.
pull tub to 250' spot cent. to sur. run 1" between
4 1/2" + 8 5/8" to app. 250' pump cent. to surface.

Plugging Proposal Received by Don Thompson
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 18:00 Day: 11 Month: 5 Year: 19 85

ACTUAL PLUGGING REPORT pumped plug down 4 1/2" cas. hole in 4 1/2"
at 100', welded 4 1/2" to 8 5/8" with 2" valve. United Cementing #10925
pumped 1400 cc com 4% gel down 4 1/2" cas. pumped 60 cc com cent. 4% gel
between 4 1/2" and 8 5/8" lit. set. pumped 400 cc com cent 4% cc.
down 4 1/2" shut well in. pumped 400 cc com cent 4% cc between
4 1/2" and 8 5/8" sur. cas. shut well in.

Remarks: _____
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 7-31-85
INV. NO. 9235

WK

RECEIVED
Signed Don Thompson
(TECHNICIAN)

JUL 26 1985
7-26-85

RO