

15-015-30178-00-01 29 R

2 030486

MAR 06 1987

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- (Docket #D-11,992)
NW, SEC. 7, T 26 S, R 3 XW/E
4290 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 6839
Operator: Woco, Inc.
Name & Address: 2225 East 21st, Ste. 205
Wichita, KS 67202
316-263-2981

Lease Name Edson Well # 2
County Butler 108.55
Well Total Depth 3340 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 201

Abandoned Oil Well Gas Well Input Well SWD Well x D&A

Other well as hereinafter indicated

Plugging Contractor Towanda Well Service License Number 5683
Address Highway 254, Towanda, Kansas

Company to plug at: Hour: 8:30 a.m. Day: 6 Month: 3 Year: 19 87

Plugging proposal received from
(company name) (phone)

were: Run tubing as far as possible, spot 50 sacks cement. Run 1" between 4 1/2" and 8 5/8" to 250' and fill with cement. Run tubing inside 4 1/2" to 250' and fill with cement.

Plugging Proposal Received by Don Thompson (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3:45 p.m. Day: 6 Month: 3 Year: 19 87

ACTUAL PLUGGING REPORT Ran 2" tubing to 1409' and United spotted 50 sacks of 60/40 poz with 3% cc. Ran 1" between 4 1/2" and 8 5/8" to 270' and pumped 150 sacks 60/40 poz and 50 sacks cement to surface. Ran 1" inside 4 1/2" to 270' and pumped 50 sacks cement to surface. PULLED 1" and 2"

STATE CORPORATION COMMISSION

MAR 12 1987
3-12-87
CONSERVATION DIVISION
Wichita, Kansas

Remarks: United Cementing Company #2090
(if additional description is necessary, use BACK of this form.)

INVOICED (11/1/87) observe this plugging.

DATE 3-16-87 WK

Signed Don Thompson (TECHNICIAN)

INV. NO. 14340 3-1 APR 10 1987