

KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2125  
Wichita, KS 67202

2-27

API NUMBER: 9/11/1929

SE SE SE SEC 9 , T 26 S, R 3E

OPERATOR LICENSE # 7741

330 FEET FROM S SECTION LINE

OPERATOR: Warren Pierce

330 FEET FROM E SECTION LINE

NAME & PO Box 353

LEASE NAME: M. Campbell WELL # 1

ADDRESS: Valley Center, KS 67147

COUNTY: Butler

WELL TOTAL DEPTH: 2771' 90.05

CONDUCTOR PIPE: 5 3/16" @ 2756'

SURFACE CASING: 6 5/8" @ 2537'

ABANDONED OIL WELL X GAS WELL \_\_\_\_\_ INPUT WELL \_\_\_\_\_ SWD \_\_\_\_\_ D&A \_\_\_\_\_

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR Sage Oil Company

ADDRESS: PO Box 12, Virgil, KS 66870 LICENSE: 5684

COMPANY TO PLUG AT: HOUR: 15:00 DAY: 27 MONTH: Feb YEAR: 1996

PLUGGING PROPOSAL RECEIVED FROM District II

COMPANY NAME: Sage Oil Company PHONE: 316-678-3880

WERE: Sand back and spot 10 sacks cement at 2761'. Shoot 5 3/16" casing at 1792' and pull out of hole. Run tubing to 250' and circulate cement slurry to surface. Pull tubing out of hole and top off with cement.

PLUGGING PROPOSAL RECEIVED BY: George Sage


PLUGGING OPERATIONS ATTENDED BY AGENT? ALL {     } PART { x } NONE {     }

COMPLETED: HOUR: 17:00 DAY: 27 MONTH: Feb YEAR: 1996

ACTUAL PLUGGING REPORT: Sanded back and spotted 10 sacks cement at 2761'. Shot 5 3/16" casing at 1792' and pulled out of hole. Shot 6 5/8" casing at 299' and pulled out of hole. Ran tubing to 250' and circulated cement slurry to surface. Pulled tubing out of hole and topped off with cement.

REMARKS: 815 Sacks Cement Slurry

I DID OBSERVE THIS PLUGGING.

  
Jerry Clark

RECEIVED  
KANSAS CORPORATION COMMISSION  
3-22-96  
MAR 22 1996  
AGENT

INVOICED

MAR 25 1996

DATE \_\_\_\_\_

INV. NO. 45115  
2-27 MAY 17 1996