

KANSAS CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
130 S. Market, Room 2125  
Wichita, KS 67202

API NUMBER: 4/4/1966

2-22

SE SW SE, SEC 9, T 26 S, R 3E

OPERATOR LICENSE # 7741

330 FEET FROM S SECTION LINE

OPERATOR: Warren Pierce

1650 FEET FROM E SECTION LINE

NAME & P.O. Box 353

LEASE NAME: Campbell WELL # 3

ADDRESS: Valley Center, KS 67147

COUNTY: Butler

WELL TOTAL DEPTH: 2810' 91.32

CONDUCTOR PIPE: 5 1/2" @ 2785'

SURFACE CASING: 8 5/8" @ 175'

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR Sage Oil Company

ADDRESS: PO Box 12, Virgil, KS 66870 LICENSE: 5684

COMPANY TO PLUG AT: HOUR: 16:00 DAY: 22 MONTH: Feb YEAR: 1996

PLUGGING PROPOSAL RECEIVED FROM District II

COMPANY NAME: Sage Oil Company PHONE: 316-678-3880

WERE: Sand back and spot 20 sacks cement at 2800'. Shoot 5 1/2" casing at 1910' and pull out of hole. Run tubing to 250' and circulate cement slurry to surface. Pull tubing out of hole and top off with cement.

PLUGGING PROPOSAL RECEIVED BY: George Sage


PLUGGING OPERATIONS ATTENDED BY AGENT? ALL {  } PART {  } NONE {  }

COMPLETED: HOUR: 17:30 DAY: 22 MONTH: Feb YEAR: 1996

ACTUAL PLUGGING REPORT: Sanded back and spotted 20 sacks cement at 2800'. Shot 5 1/2" casing at 1910' and pulled out of hole. Ran tubing to 250' and circulated cement slurry to surface. Pulled tubing out of hole and topped off with cement.

REMARKS: 110 Sacks Cement Slurry

I DID OBSERVE THIS PLUGGING.

  
Jerry Clark

RECEIVED  
KANSAS CORPORATION COMMISSION  
MAR 22 1996  
3-22-96  
CONSERVATION DIVISION  
WICHITA, KS  
AGENT

INVOICED

DATE MAR 25 1996

INV. NO. 45114

2-22 MAY 17 1996