

KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2125
Wichita, KS 67202

2-20

API NUMBER: 15-015-21,567 ⁻⁰⁰⁻⁰¹ E-20,425

SE NE SE SEC 9, T 26 S, R 3E

OPERATOR LICENSE # 7741

1650 FEET FROM S SECTION LINE

OPERATOR: Warren Pierce

330 FEET FROM E SECTION LINE

NAME & P.O. Box 353

LEASE NAME: Campbell "B" WELL # 3

ADDRESS: Valley Center, KS 67147

COUNTY: Butler

WELL TOTAL DEPTH: 2850' 92.63

CONDUCTOR PIPE: 4 1/2" @ 2849'

SURFACE CASING: 8 5/8" @ 204'

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL X SWD _____ D&A _____ E-20,425

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR George Sage

ADDRESS: P.O. Box 12, Virgil, KS 66870 LICENSE: 5684

COMPANY TO PLUG AT: HOUR: 10:30 DAY: 20 MONTH: Feb YEAR: 1996

PLUGGING PROPOSAL RECEIVED FROM District 2

COMPANY NAME: Sage Oil Company PHONE: 316-678-3880

WERE: Sand back and spot 16 sacks cement at 2538'. Shoot 4 1/2" casing at 1545' and pull out of hole. Run tubing to 250' and circulate cement to surface. Pull tubing out of hole and top off with cement.

PLUGGING PROPOSAL RECEIVED BY: George Sage


PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { } PART { X } NONE { }

COMPLETED: HOUR: 12:00 DAY: 20 MONTH: Feb YEAR: 1996

ACTUAL PLUGGING REPORT: Sanded back and spotted 16 sacks cement at 2538'. Shot 4 1/2" casing at 1545' and pulled out of hole. Ran tubing to 250' and circulated cement to surface. Pulled tubing out of hole and topped off with cement.

REMARKS: 93 Sacks Cement. 60/40 Poz

I DID OBSERVE THIS PLUGGING.


Jerry Clark

RECEIVED
KANSAS CORPORATION COMMISSION
3-5-96
MAR 05 1996

AGENT
CONSERVATION DIVISION
WICHITA, KS
FORM CP-2/3
REV. 3/90

INVOICED
DATE MAR 06 1996
INV. NO. 44970

2-20- MAY 17 1996

DW