

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

8-2

API NUMBER: 15-015-21,589-00-00

SE NE NE, SECTION 10 TOWNSHIP 26 RANGE 3E

OPERATOR LICENSE # 4336 4290 FEET FROM S SECTION LINE
OPERATOR GOBEN'S UNITED PETROLEUM INC 330 FEET FROM E SECTION LINE
NAME & 3223 ENGLISH
ADDRESS WICHITA, KS 67218 LEASE NAME: NOVASCONE #2
COUNTY: BUTLER 91.00
WELL TOTAL DEPTH: 2800'
PIPE: 4 1/2" @ 2799'
SURFACE CASING: 8 5/8" @ 200'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: KC DEVELOPMENT INC
ADDRESS: R.R. 1, BOX 56, FLORENCE, KS 66851 LICENSE: 30111

COMPANY TO PLUG AT: HOUR: 14:30 DAY: 2 MONTH: 8 YR: 1996

PLUGGING PROPOSAL RECEIVED FROM: DISTRICT II
COMPANY NAME: CONCRETE PRODUCTS INC PHONE: (316) 947-2253
WERE: SAND BACK AND SPOT 5 SACKS OF CEMENT AT 2680'. SHOOT 4 1/2" CASING AT 2300' AND PULL OUT OF HOLE. RUN TUBING TO 250' AND CIRCULATE CEMENT SLURRY TO SURFACE. PULL TUBING OUT OF HOLE AND TOP OFF WITH CEMENT.

RECEIVED
KANSAS CORPORATION COMMISSION

PLUGGING PROPOSAL RECEIVED BY: REX SAVAGE

AUG 29 1996

8-29-96

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE WICHITA, KS

COMPLETED: HOUR: 17:00 DAY: 2 MONTH: 8 YEAR: 1996

ACTUAL PLUGGING REPORT: SANDED BACK AND SPOTTED 5 SACKS OF CEMENT AT 2650'. SHOT 4 1/2" CASING AT 2300' AND PULLED OUT OF HOLE. RAN TUBING TO 250' AND CIRCULATED CEMENT SLURRY TO SURFACE. PULLED TUBING OUT OF HOLE AND TOPPED OFF WITH CEMENT.

REMARKS: 55 SACKS OF CEMENT SLURRY CONCRETE #29135

I DID OBSERVE THIS PLUGGING.

JERRY CLARK

INVOICED

DATE AUG 30 1996

INV. NO. 43717

8-2

OCT 17 1996