

API NUMBER 15-015-19957-00-00

LEASE NAME Campbell

WELL NUMBER #2

         Ft. from S Section Line

         Ft. from E Section Line

SEC. 9 TWP. 26 RGE. 3E (E) or (W)

COUNTY Butler

Date Well Completed 2-29-64

Plugging Commenced 2-20-96

Plugging Completed 2-21-96

TYPE OR PRINT  
 NOTICE: Fill out complotoly  
 and return to Cons. Div.  
 office within 30 days.

LEASE OPERATOR Warren Pierce

ADDRESS P O Box 353

PHONE# (316) 755-1385 OPERATORS LICENSE NO. 07741

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-20-96 (date)

by Jerry Clark (KCC District Agent's Name).

Is ACO-1 filed? no If not, Is well log attached? yes

Producing Formation          Depth to Top          Bottom          T.D.         

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	200'	none
				4 1/2	2790	1936

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from          feet to          feet each set  
Pump 16 sax cement through tubing at 2750', Shot pipe at 1936, pulled pipe  
Ran 250' tubing, circulate cement to surface. 140 sax cement. Total cement this well 156 sax.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor George Sage License No. 5684

Address Box 12 Virgil, Kansas 66870

RECEIVED  
 KANSAS CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Warren Pierce

STATE OF Kansas COUNTY OF Sedgewick, ss.

JUN 13 1996  
 6-13-96

George Sage (Employee of Operator          or above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) George Sage

(Address) Box 12 Virgil, Kansas

SUBSCRIBED AND SWORN TO before me this 14th day of March, 1996

Kelly Sage  
 Notary Public

KELLY SMYE Comm  
 NOTARY PUBLIC  
 STATE OF KANSAS

KELLY SAGE  
 NOTARY PUBLIC  
 STATE OF KANSAS  
 4/24/97

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

COPY


Company- Se Robee Drilling Co. Inc.  
Farm- Campbell No. 2

SEC. 9 T. 26 R. 3E  
SW SW SE

Total Depth. 2809'  
Comm. 2-22-64 Comp. 2-29-64  
Shot or Treated.  
Contractor. Se Robee Drlg.  
Issued. 5-2-64

County Butler  
KANSAS

K. W. WOODBURY



CASING:

8" 200' cem w/ 125 sx  
4" 2790' cem w/ 60 sx

Elevation. 1346' GL

Production. 25 BOPD

Figures Indicate Bottom of Formations.

top soil, lime & shale	95
lime & shale	550
lime	645
lime & shale	1135
shale & shells	1280
lime & shale	1420
lime	1530
lime & shale	2176
lime	2257
lime & shale	2325
Kansas City	2490
lime	2777
Conglomerate	2788
Mississippian	2809 RTD
Total Depth	

TOPS:SMP	
Kansas City	2325
Base Kansas City	2490
Conglomerate	2777
Mississippian	2788

RECEIVED  
KANSAS CORPORATION COMMISSION

JUN 13 1996

CONSERVATION DIVISION  
WICHITA, KS