


15-015-00253-00-00

State  
STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

### WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Butler County. Sec. 9 Twp. 26S Rge. 3 (E) E (W)  
Location as "NE/CNW/SW" or footage from lines NW NE SE  
Lease Owner Rex & Morris, Etal  
Lease Name Straw Well No. 1  
Office Address Box 334, El Dorado, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed Sept. 26 1956  
Application for plugging filed " 19 "  
Application for plugging approved " 19 "  
Plugging commenced " 19 "  
Plugging completed " 19 "  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Lawrence W. Matthews, El Dorado, Kansas  
Producing formation Miss. Chat Depth to top 2753 Bottom 2767 Total Depth of Well 2775 Feet  
Show depth and thickness of all water, oil and gas formations.

#### OIL, GAS OR WATER RECORDS

#### CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Hole	Water	0	104	8 5/8"	104	None
Miss. Chat	Oil & Water	270	2753	5 1/2"	2753'	2360
See Attached Log						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Dumped Plastic from 2775 to 2763: Dumped 5 sacks of cement on bottom: Mud to 140': Set 15 Sacks of cement on 10' Rock Bridge at 130': Mud to surface: Set 5 Sacks of cement cap.

**RECEIVED**  
STATE CORPORATION COMMISSION  
OCT 15 1956  
10-13-56  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Rex & Morris Drilling Company  
Address Box 334, El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.  
C. E. McClure (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. E. McClure  
Box 334, El Dorado, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of October, 1956  
Winifred E. Cruitt  
Winifred E. Cruitt Notary Public.  
My commission expires July 23, 1960

**PLUGGING**  
FILE SEC 9 T. 26 R. 3E  
BOOK PAGE 103 LINE 39

Elevation 1335 DF  
1338 RB

STRAW WELL # 1

REX & MORRIS - ET AL

Total Depth	- 2775	
Contractor	- Rex & Morris Drilling Co.	Location - NW NE SE
Commenced	- 8-13-56	Section 9-26S-3E
Completed	- 9-26-56	Butler County, Kansas
Initial Production	- D & A	

Casing Record:  
 8 5/8" @ 104' w/ 160 sacks  
 5 1/2" @ 2753 w/ 50 sacks  
 (Pulled 2360')

FORMATION	DEPTH
Shale	25
Lime Sandy (HFW)	35.
Shale	45
Lime	50
Shale	70
Lime	75
Shale (Pink)	85
Lime	100
Shale (Surface Hole)	106
Lime & Shale	755
Shale & Lime	1795
Lime & Shale	2025
Lime	2165
Shale & Lime	2306
Lime	2478
Lime & Shale	2753
Chat	2767
Lime R. T. D.	2775 RB
R. U. S. T. & D. P. & C. P. RTD	2772 DF
Test 465' fluid in 16 hrs. (28 gal. water)	
Test @ 88 B. O. P. H. Test 425' fluid (10 gal. water & 9 1/2 BO) in 16 hrs.	
ACID Petro-Frac w/ 5000 gal. & 5000# sand.	
Used 189 B. load oil. Swab down recovered 80 BW and 84 BO.	
Final test, 42 BW P. H. w/ small amount of oil	
Plug back w/ plastic to	2760
Test approximately 18 BW PH w/ trace oil	
Plug and abandoned.	

I hereby certify the foregoing statements are true and correct to the best of my knowledge and belief.

Rex & Morris Drilling Company

By Paul D. Hoony

Title Geologist

STATE OF KANSAS )  
 ) SS.  
 COUNTY OF BUTLER )

Subscribed and sworn to before me, a Notary Public, this 12 day of October 1956.

Winifred E. Cruik  
Winifred E. Cruik - Notary Public

My commission expires;  
July 23, 1960

PLUGGING
FILE SEC 9 T. 26 R. 3E
BOOK PAGE 103 LINE 39