

API NUMBER 15-015-30310-00-00

LEASE NAME Campell

WELL NUMBER #3

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 9 TWP. 26 RGE. 3 (E) or (W)

COUNTY Butler

Date Well Completed 4-4-66

Plugging Commenced 2-21-96

Plugging Completed 2-22-96

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Warren Pierce

ADDRESS PO. Box 353

PHONE# (316) 755-1385 OPERATORS LICENSE NO. 07742

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-21-96 (date)

by Dave Wertz (KCC District Agent's Name).

Is ACO-1 filed? no If not, Is well log attached? yes

Producing Formation Depth to Top Bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	175'	none
				5 1/2	2785	1910

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set. Pump 20sax cement through tubing at 2775'. Shot pipe at 2146 would not pull, shot pipe at 1910' pipe pulled. Run 2 3/8 tubing to 250' circulate cement to surface 150 sax. 170 sax total this well.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor George Sage License No. 5684

Address Box 12, Virgil, Kansas 66870

RECEIVED
 KANSAS CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Warren Pierce

STATE OF Kansas COUNTY OF Sedgewick, ss. JUN 13 1996
6-13-96

George Sage (Employee of Operator CONSERVATION DIVISION) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) George Sage

(Address) Box 12 Virgil, Kansas 66870

SUBSCRIBED AND SWORN TO before me this 14th day of March, 19 96

Kelly Sage Notary Public

My Commission Expires: 4/24/97



KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS

COPY

COMPANY SE RO BEE DRILLING

SEC. 9 T. 26 R. 3E

FARM Campbell

NO. X 3

LOC. C E $\frac{1}{2}$ SW SE

TOTAL DEPTH 2810'

COUNTY Butler

COMM. 3-29-66


COMP. 4-4-66

KANSAS

SHOT OR TREATED

CONTRACTOR Se Ro Bee Drilling

K. G. S. LIBRARY



ISSUED 5-14-66

CASING

20	10	
15	8 5/8" 175'	cem w/ 150 sx
12	6	
13	5 1/2" 2785'	cem w/ 75 sx

ELEVATION 1357' KB

PRODUCTION 25 BOPD

FIGURES INDICATE BOTTOM OF FORMATIONS

0 - 580	Lime
580 - 1665	Lime & Shale
1665 - 1735	Lime
1735 - 2255	Lime & Shale
2255 - 2711	Lime
2711 - 2784	Lime & Shale
2784 - 2810	Chat

Geological Tops

K. C.	2323	(-966)
Base-KC	2491	(-1134)
Cherokee	2717	(-1360)
Conglomerate	2776	(-1419)
Miss.	2784	(-1427)
Total Depth	2710	(-1453)

I certify the above to be a true and correct copy of the driller's log and geological tops to the best of my knowledge and belief.

SEROBEE DRILLING CO., INC.

Paul S. Septer

Paul S. Septer, President