

API NUMBER 15-015-21567-00-01

LEASE NAME Campbell B

WELL NUMBER #3

 Ft. from S Section Line

 Ft. from E Section Line

SEC. 9 TWP. 26 RGE. 3E (E) or (W)

COUNTY Butler

Date Well Completed 11-17-80

Plugging Commenced 2-19-96

Plugging Completed 2-20-96

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Warren Pierce

ADDRESS P O Box 353

PHONE # (316) 755-1385 OPERATORS LICENSE NO. 07741

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-18-96 (date)

by Jerry Clark (KCC District Agent's Name).

Is ACO-1 filed? no If not, Is well log attached? yes

Producing Formation Depth to Top Bottom T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	204	none
				4 1/2	2849	1545

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set Pump 16 sax cement through tubing at 2528', shot pipe at 1545, pulled pipe.
Circulate cement to surface, through tubing 250' 93 sax. total cement this well 109 sax

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor George Sage License No. 5684

Address Box 12 Virgil, Kansas 66870

RECEIVED
 KANSAS CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Warren Pierce

STATE OF Kansas COUNTY OF Sedgewick, ss.

George Sage

(Employee of Operator or Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) George Sage

(Address) Box 12 Virgil, Kansas

SUBSCRIBED AND SWORN TO before me this 14th day of March, 19 96

Kelly Sage
 Notary Public

My Commission Expires:

KIRIBLY SAGE
 NOTARY PUBLIC
 WICHITA, KANSAS

KELLY SAGE
 NOTARY PUBLIC
 STATE OF KANSAS
 MY APPT. EXPIRES 4/24/97

K. G. S. LIBRARY

WELL LOG

State Geological Survey
WICHITA BRANCH

7-26-24
SE-NW-SE

Company W. R. Pierce
 Farm Campbell B
 Well 3
 Location SE NW SE 9 26S 3E Burlter Co. , Ks.
 Commenced 11/10/80
 Completed 11/17/80
 Casing 204' 8 5/8" cemented with 125 sacks
 2849' 4 1/2" cemented with 100 sacks
 Contractor Jackma & Jackman
 Production Testing
 Total Depth 2850'

Soil & Clay	0	-	30
Shale & Lime	30		70
Lime & Shale	70		170
Lime	170		212
Lime & Shale	212		1370
Shale & Lime	1370		1595
Lime & Shale	1595		2009
Lime	2009		2201
Shale	2201		2410
Lime	2410		2470
Shale	2470		2582
Shale & Shells	2582		2748
Shale	2748		2779
Lime	2779		2850

0' is 4' above ground level.

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 13 1996

CONSERVATION DIVISION
WICHITA, KS

W.R. PIERCE
208 W. MAIN
VALLEY CENTER, KS
CONTR JACKMAN & JACKMAN #B-3 CAMPBELL 9-26S-3E
CTY BUTLER SE NW SE
GEOL DEAN SEEBER FIELD BENTON

55

E 1552 EKB CM 11/11/80 CARD ISSUED 12/18/80 IP P 15 80 & 70 BWPD
API 15-015-21,567 MISS 2786-2797

+	+
+	+
+	+

SMP	TOPS	DEPTH	DATUM.
CONG	2769	-1217	
MISS CHT	2779	-1227	
MISS DOL	2788	-1236	
MISS LM	2806	-1254	
RTD	2850	-1298	

8-5/8" 217, 4 1/2" 2850
NO DST'S
MICT - CO, PF (MISS) 2786-97, NAT, POP

ELEY 1552

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

RECEIVED
KANSAS CORPORATION COMMISSION

JUN 13 1996

CONSERVATION DIVISION
WICHITA, KS