

STATE OF KANSAS
STATE CORPORATION COMMISSION
30 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-015-21588-00-00

LEASE NAME NOOASCONE

WELL NUMBER #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

4950 Ft. from (S) Section Line

990 Ft. from (E) Section Line

SEC. 10 TWP. 26 RGE. 3 (E) or (W)

COUNTY BUTLER

LEASE OPERATOR GOBEN'S UNITED PET. INC

ADDRESS 3223 ENGLISH WICHTA, KS.

PHONE: (316) 6860227 OPERATORS LICENSE NO. 4336

Date Well Completed 8/13

Plugging Commenced 8/13/96

Plugging Completed 8/13/96

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on _____ (date)

by _____ (KCC District Agent's Name).

is ACO-1 filed? _____ If not, is well log attached? WAS W/ CP-1

Producing Formation MISS. Depth to Top 2720 Bottom 2722 T.D. 2757

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD 10-24-96

| Formation | Content | From | To | Size | Put In | Pulled out |
|-------------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 200' | NONE |
| | | | | 4 1/2 | 2756' | 1800' |
| BRIDGE PLUG | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

SAND BACK + SPOT 5 SACKS CEMENT @ 2650'. SHOOT 4 1/2 CASING @ 1800'.
AND PULLED. RAN TUBING TO 260' + CIRCULATED CEMENT
SLURRY TO SURFACE. PULL TUBING OUT OF HOLE
AND TOP OFF WITH CEMENT. 92 SACKS OF CEMENT

Name of Plugging Contractor KC DEVELOPMENT License No. 30111

Address #1 Box 510 FLORENCE, KS 66851

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: GOBEN'S UPI

STATE OF KANSAS COUNTY OF SEDGWICK, ss.


DAVID S. LANGSTON (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 3223 English 67218

SUBSCRIBED AND SWORN TO before me this 23 day of Oct, 19 96

Karen S. Caudillo
Notary Public



Expires: 2-27-2000