

**\* STATE OF KANSAS  
STATE CORPORATION COMMISSION**

**Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas**

## WELL PLUGGING RECORD

**Butler**

County. Sec. 10 Twp. 26S Rge. 3 (E).....(W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines NW NE SW

Lease Owner B. V. Cox, et al

Lease Name Glancey "A" Well No. 1

Office Address.....425 S. Main St., El Dorado, Kansas.....

Character of Well (completed as Oil, Gas or Dry Hole) ..... **Dry Hole** .....

Date well completed..... April 7 19 51

Application for plugging filed..... **Verbal** ..... **April 7** ..... 19 **51**

Application for plugging approved..... **Verbal** ..... **April 7** ..... 19 **51**

Plugging commenced ..... April 7 1951

Plugging completed..... April 7 1951

Reason for abandonment of well or producing formation..... **Dry hole**

If a producing well is abandoned, date of last production..... 19.....

Was permission obtained from the Conservation Division or its agents before plugging was com-

menched? Yes

d plugging of this well.....A. L. Loman, El Dorado, Kansas.....

..... Depth to top..... Bottom..... Total Depth of Well.....2834.....Feet

and gas formations.

## OIL, GAS OR WATER RECORDS

## CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with rotary mud to 200'. Cemented with 15 sax cement on wooden plug.  
Filled with mud to surface and capped with 5 sax cement.

STATE CORPORAL  
4-16-51  
APR 16 1951  
OBSERVATION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to..... **B. V. Cox, et al**

Address..... 425 S. Main St., El Dorado, Kansas

STATE OF KANSAS, COUNTY OF BUTLER, ss.

.....(employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-  
described well as filed and that the same are true and correct. So help me God. *2.1*

(Signature) 

.....  
(Address)

SUBSCRIBED AND SWORN TO before me this 14 day of April, 1951

My commission expires.

23-3273-S 4-50-10M

FILE SEC. 10 T 86 R 36  
BOOK PAGE 74 LINE 30

WELL LOG - Glancey #A-1

OPERATOR: B. V. Cox, et al  
425 South Main Street  
El Dorado, Kansas

LOCATION: NW NE SW  
Section 10-26S-3E  
Butler County, Kansas

CONTRACTOR: Morrison Drilling Company, Inc.  
Drawer 712  
El Dorado, Kansas

PRODUCTION: D & A

Farm: Glancey "A" Well No. 1

Date Commenced: March 30, 1951

Date Completed: April 7, 1951

Total Depth: 2834' - Rotary

| <u>From</u> | <u>To</u> | <u>Formation</u>    |
|-------------|-----------|---------------------|
| 40          | 100       | Cement              |
| 100         | 210       | Lime                |
| 210         | 375       | Lime - broken       |
| 375         | 495       | Broken Lime & Shale |
| 495         | 930       | Shale & Shells      |
| 930         | 975       | Shale & Lime brks.  |
| 975         | 1050      | Sandy Shale         |
| 1050        | 1255      | Lime & Shale        |
| 1255        | 1350      | Broken Lime & Shale |
| 1350        | 1438      | Lime & Shale        |
| 1438        | 1570      | Shale               |
| 1570        | 1615      | Lime & Shale        |
| 1615        | 1700      | Lime                |
| 1700        | 1898      | Lime & Shale        |
| 1898        | 1980      | Shale               |
| 1980        | 1990      | Lime                |
| 1990        | 2015      | Shale               |
| 2015        | 2170      | Lime                |
| 2170        | 2230      | Lime & Shale        |
| 2230        | 2270      | Broken Lime & Shale |
| 2270        | 2303      | Shale               |
| 2303        | 2315      | Lime - broken       |
| 2315        | 2445      | Lime                |
| 2445        | 2504      | Lime & Shale brks.  |
| 2504        | 2514      | Lime                |
| 2514        | 2544      | Lime                |
| 2544        | 2628      | Broken Lime & Shale |
| 2628        | 2780      | Shale               |
| 2780        | 2785      | Lime - cherty       |
| 2785        | 2834      | Lime                |
| 2834        |           | Total Depth.        |

I hereby certify that the foregoing is a true and correct copy of the Well Log for the Glancey "A" -1 well drilled for B. V. Cox, et al and completed April 7, 1951.

MORRISON DRILLING COMPANY, INC.

  
C. W. Wilson - Secretary-Treasurer

STATE OF KANSAS

COUNTY OF BUTLER

ss.

SUBSCRIBED AND SWORN TO, Before the Undersigned, a Notary Public, in and for the County and State aforesaid this 10th day of April, 1951.

  
Notary Public

My Commission Expires January 10, 1955.

