

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division,
State Corporation Commission,
800 Bitting Building,
Wichita, Kansas.

NORTH

X			

Locate well correctly on above
640 A. Plat

WELL PLUGGING RECORD JUN 7 1937

OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging off formations.

Butler County. Sec. 10 Twp. 26 Rge. 3 (E) (W)

Lease Name. Clancey WELL NO. 1

Lease Owner. R. J. Wixson et al

Office Address. Box 82, El Dorado, Kansas

Character of Well (Oil, Gas or Dry) Dry Total Depth of Well. 2845 Feet

Date, well, completed. May 13, 1937 19

Application for plugging and log of well filed. May 8, 1937 193

Application for plugging approved. May 8, 1937 193

Plugging Commenced. May 8, 1937 193

Plugging Completed. May 13, 1937 193

Reason for abandonment of well or producing formation. Dry Hole

If a producing well is abandoned, date of last production.....193.....
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced?.....Yes.....

Name of Conservation Officer who supervised plugging of this well..... **Eldon Petty**
Producing formation..... Depth to top..... Bottom **2845**

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASTING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Lime	H F W	55	60	12½"	64'	64'
Sand	7 B W	930	940			
Sand	H F W	1050	1085	10"	1250'	1250'
Lime	2 B W	1475				
Sandy Lime	5 B W	1835	1855			
Sandy Lime	H F W	2080	2095	8½"	2111'	2111'
Sandy Lime	H F W	2380	2390	6-5/8"	2414'	2414'
Sandy Lime	3 B W	2440	2440	5-3/16"	2770'	2770'


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Plugged with 60 buckets of mud to 2770'.

Pulled 5-3/16" and filled hole with 100 buckets of mud

Bridged at 110' with wood plug and 10' of rock and mud and cemented at 100' with 10 sacks of cement

Bridged with wood plug at 15', put in rock and cemented with 5 sacks of cement. Filled with mud to surface



(If additional description is necessary use BACK of this sheet)

Does the above conform strictly to the Conservation Division regulations?.....Yes

Was exception made?..... If so describe.

Correspondence regarding this well should be addressed to R. J. Wixson

Address..... Box 82, El Dorado, Kansas.

STATE OF KANSAS COUNTY OF BUTLER, ss.

R. J. Wixson

.....R. J. Wixson.....(employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God.

(Signature).

God.
R. J. Hipsan

Box 82, El Dorado, Kansas
(Address)

(Address

SUBSCRIBED AND SWORN to before me this 25 day of May, 19 37

My commission expires May 22, 1939.

.....
Notary Public.

SW Corner NW $\frac{1}{4}$ SW $\frac{1}{4}$ Section 10 - 26 - 3E BUTLER COUNTY, KANSAS


Begun: April 3, 1937

Completed: May 8, 1937

Formation	From	To	Formation	From	To
Sand	0	25	slate	1085	1105
sandy shale	25	50	lime	1105	1110
lime	50	70	shale	1110	1135
H F W @ 55-60			lime	1135	1140
Set 12 $\frac{1}{2}$ " @ 64'			slate	1140	1155
shale	70	90	lime	1155	1160
lime	90	100	shale	1160	1205
slate	100	160	sand	1205	1235
lime	160	320	shale	1235	1245
slate	320	330	lime	1245	1255
lime	330	340	Set 10" @ 1250'		
slate	340	345	shale	1255	1280
lime	345	355	lime	1280	1300
lime & shale	355	410	$\frac{1}{2}$ B W @ 1290'		
red rock	410	420	slate	1300	1310
lime	420	425	lime	1310	1330
shale	425	455	shale	1330	1395
lime	455	460	lime	1395	1445
slate	460	470	shale	1445	1465
lime	470	480	lime	1465	1500
shale & lime	480	525	2 B W @ 1475'		
shale	525	535	shale	1500	1505
lime	535	550	lime	1505	1550
shale	550	585	shale	1550	1555
lime	585	600	lime	1555	1595
slate	600	630	shale	1595	1600
lime	630	645	lime	1600	1695
shale	645	655	shale	1695	1705
lime	655	695	lime	1705	1765
shale	695	705	shale	1765	1815
lime	705	720	lime	1815	1820
shale	720	735	shale	1820	1835
lime	735	740	sandy lime	1835	1855
shale	740	830	5 B W @ 1835-1855		
lime	830	835	shale	1855	1925
shale	835	875	lime	1925	1935
lime	875	880	shale	1935	1940
shale	880	890	lime	1940	1960
lime	890	900	shale	1960	1975
slate	900	925	lime	1975	2010
lime	925	930	sandy shale	2010	2030
sand	930	940	lime	2030	2080
7 B W @ 930-940			sandy lime	2080	2095
sandy shale	940	945	H F W @ 2080-2095		
sandy lime	945	950	sand	2095	2100
shale	950	970	lime	2100	2135
lime	970	980	Hole Correction back from		
shale	980	990	2120 to 2111		
sandy shale	990	1050	Set 8 $\frac{1}{4}$ " @ 2111'		
sand	1050	1085	shale	2135	2150
H F W @ 1050-1085			lime	2150	2195
			shale	2195	2220

Formation	From	To	Formation	From	To
sandy shale	2220	2255	sandy shale	2535	2545
slate & shells	2255	2310	shale	2545	2560
shale	2310	2320	lime	2560	2575
lime	2320	2340	slate	2575	2590
shale	2340	2350	lime	2590	2600
lime	2350	2380	lime shells	2600	2615
sandy lime	2380	2395	shale	2615	2630
H F W @ 2380-2390			lime	2630	2680
lime	2395	2400	lime & shale	2680	2730
sand	2400	2405	lime	2730	2740
lime	2405	2435	shale	2740	2765
Set 6-5/8" @ 2412'			lime	2765	2796
sandy lime	2435	2465	Set 5-3/16" @ 2770'		
3 B W @ 2440-2450			shale green	2796	2800
lime	2465	2490	lime	2800	2845
shale	2490	2535	Show Oil @ 2840-2842		
				Total Depth	2845

I hereby certify that the above log is true and correct to the best of my knowledge and belief.



Subscribed and sworn to before me this the _____ day of _____, 1937.

My commission expires

Notary Public.