

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER #15-015-22082-00-00

LEASE NAME Ken Lygrisse

WELL NUMBER 1

SPOT LOCATION 330 FSL 230 FWL

SEC. 18 TWP. 26 RGE. 3 (E) or (W)

COUNTY Butler

Date Well Completed 7-16-82

Plugging Commenced 9-24-84

Plugging Completed 9-27-84

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Benjamin M. Giles

ADDRESS 321 E. William Wichita, Ks. 67202

PHONE # (316) 262-4496 OPERATORS LICENSE NO. 5446

Character of Well Oil  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Wichita

Is ACO-1 filed? Yes If not, is well log attached? \_\_\_\_\_

Producing formation Hunton Depth to top 3195 bottom 3226 T.D. 3305

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	203	-0-
	See att. Geo. log			8 1/2	3300	2333

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set. Done per Davids instructions at KCC.

94ft. of sand dumped in hole from 3234 (bottom plug) to 3140 - Cemented with 5 sax of cement. Set plug at 300 ft. - put in 30ft. of rock on top of plug & cemented to top with redi mix.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Towanda Well Service License No. \_\_\_\_\_

Address Box 337 Towanda, Ks. 67144

RECEIVED

STATE CORPORATION COMMISSION

, ss.

11-13-84

NOV 13 1984

STATE OF Kansas COUNTY OF Sedgwick

Benjamin M. Giles

(employee of operator) of

(operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Benjamin M. Giles

(Address) 321 E. William Wichita, Ks. 67202



SUBSCRIBED AND SWORN TO before me this 9 day of November, 1984

Ronald R. Marsh  
Notary Public

My Commission expires: 12-14-86

W.  
PAT  
SIMMONS

P  
E  
T  
R  
O  
L  
E  
U  
M  
G  
E  
O  
L  
O  
G  
I  
S  
T

DRILLING PROSPECTS — OIL & GAS INVESTIGATIONS — WELL SUPERVISION — WELL COMPLETIONS  
5252 NORTH BROADWAY • WICHITA, KANSAS 67219 • 316 838-3761

GEOLOGIC REPORT

Giles Oil Company  
#1 Lygrisse  
330' FSL & 230' FWL of SW/4  
Approximately SW SW SW  
Section 18-26S-3E  
Butler County, Kansas

Commenced: 7/8/82  
Completed: 7/16/82

July 28, 1982

Elevation: 1390 RB

Casing Record:  
8 5/8" @ 203'/150 sax.  
5 1/2" @ 3300'/100 sax.

Development Well  
I.P. - Pending

SUMMARY OF FORMATIONS

Lansing	2190 (-800)
Kansas City	2398 (-1008)
Base of Kansas City	2568 (-1178)
Mississippian	2844 (-1454)
Kinderhook	3150 (-1760)
Hunton	3195 (-1805)
Viola	3226 (-1836)
Simpson Shale	3266 (-1876)
Simpson Sand	3182 (-1892)
Simpson Sand	3295 (-1905)
Rotary Total Depth	3305 (-1915)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 13 1984  
CONSERVATION DIVISION  
Wichita, Kansas