

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Paul Turpin

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from 200 feet to 3173 feet for each plug set.

each plug set.
Mud from total depth to 200 ft. -- $\frac{1}{2}$ sk. hulls and plug and 15 sks. cement -- Mud to 30 ft. -- $\frac{1}{2}$ sk. hulls -- plug and 8 sks. cement -- 2 sks. in rathole.

RECEIVED
STATE CORPORATION COMMISSION

JUN 25 1963

6-25-63

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor German Drilling Company

Address 502 Petroleum Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.
Harvey F. German (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) Harvey F. German
502 Petroleum Building, Wichita 2, Kansas
 (Address)

Harvey F. German
502 Petroleum Building, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 24th day of June, 1963

of June, 1965
Geneva M. German
 Geneva M. German -Notary Public.

My commission expires December 29th, 1963.



WELL LOG -- Manspeaker #1

OPERATOR: John P. Gaty
Suite 204
4601 East Douglas
Wichita, Kansas

LOCATION: SW NW SE
19-26-3E
Butler County
Kansas

CONTRACTOR: German Drilling Company
502 Petroleum Building
Wichita 2, Kansas

Farm: Manspeaker
Date Commenced: 6-14-63
Date Completed: 6-21-63

Well No. 1
Rotary

RECEIVED
STATE CORPORATION COMMISSION
JUN 25 1963

From	To	Formation
0	70	Shale and sand
70	130	Lime
130	190	Lime
190	510	Lime
510	965	Shale and lime
965	1470	Shale and shells
1470	1670	Shale and lime
1670	1963	Shale and lime
1963	2210	Broken lime and shale
2210	2370	Lime and shale
2370	2418	Lime and shale
2418	2492	Lime (Kansas City)
2492	2550	Lime
2550	2665	Lime and shale
2665	2790	Lime and shale
2790	2825	Lime and shale
2825	2874	Chat (Mississippi)
2874	2945	Lime and chert
2945	2988	Lime
2988	3021	Lime
3021	3067	Shale and lime
3067	3125	Lime and shale
3125	3154	Lime and shale
3154	3167	Lime (Hunton)
3167	3173	Viola
3173		Total Depth

I hereby certify that the foregoing is a true and correct copy of the Well Log for the Manspeaker No. 1, drilled for John P. Gaty and completed June 21st, 1963.

GERMAN DRILLING COMPANY

By Harvey F. German
Harvey F. German-Owner

STATE OF KANSAS)
COUNTY OF BUTLER) ss.

Subscribed and sworn to, before the undersigned a Notary Public in and for County and State aforesaid this twenty-fourth day of June, 1963.

Geneva M. German
Geneva M. German-Notary Public

My commission expires December 29th, 1963.

