



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
08-05-1969
AUG 5 1969
CONSERVATION DIVISION
Wichita, Kansas

15-065-00342-00-01

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Joe Clarke of Southwest Csg. Pulling Co., has this date requested permission to plug the following described well:

Mr. Clarke guarantees payment of the plugging fee.

Operator's full Name: Commercial Oil, Incorporated.

Complete Address: 5252 North Broadway, Wichita, Kansas.

Lease Name: Noah "E"-Grecian Well No. 1

Location: NE-NE-SW Sec. 16 Twp. 10 Rge. (E)(W) 21

County: Graham Total Depth 3815' - Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Clarke was instructed to plug the well as follows:

165'--8 5/8" Surface casing, cement circulated with 100 Sx.
3650'--4 1/2" Production casing cemented on bottom with 150 Sx. Well plugg-
ed back to 3465'. Top perforations from 3440' to 3445'.

Sand well back to 3440' and set 3 Sx. cement with dump bailer. Pull 1 1/2"
casing and squeeze well with 5 sacks hulls, 30 sacks gel and 130 Sx.
cement, staged.

Very truly yours,

W. L. Nichols
Conservation Division Agent