



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 10 1973
12-10-1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock 15-065-20564-00-00
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Darrell Kelso of Kelso Casing Pulling, has this

date requested permission to plug the following described well:

Mr. Kelso guarantees payment of the plugging fee.

Operator's full Name: Murfin Drilling Company,

Complete Address: 617 Union Center, Wichita, Kansas.

Lease Name: Grecian Well No. 1

Location: E/2-SW-NE Sec. 17 Twp. 10 Rge. (E)(W) 21

County: Graham Total Depth 3897' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Kelso was instructed to plug the well as follows:

177'--8 5/8" Surface casing, cement circulated with 135 Sx.
3893'--5 1/2" Production casing cemented on bottom with 150 Sx. Well plugged
back to 3826', No perforations indicated. Check fluid level if below 3500'
set wood and rock bridge @ top of fluid and 5 Sx. cement with dumpbailer.
Pull 5 1/2" casing and squeeze well with 5 sacks hulls, 25 sacks gel and 150
Cu. Ft. cement, staged.

Very truly yours,

K. L. Dehels
Conservation Division Agent