

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-065-00342-00-01

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 5 1969  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Commercial Oil, Incorporated,

Complete Address 5252 North Broadway, Wichita, Kansas.

Lease Name Noah "E"--Grecian Well No. 1

Location NE-NE-SW Sec. 16 Twp. 10 Rge. (E) (W) 21

County Graham Total Depth 3815'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Southwest Casing Pulling Company, Incorporated,

Address Box #364, Great Bend, Kansas. License No. 399

Operation Completed: Hour 5:00 PM Day 1 Month 8 Year 1969

The above well was plugged as follows:

165'--8 5/8" Surface casing, cement circulated with 100 Sx.

3650'--4 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to 3465'. Top perforations from 3440' to 3445'.

Sanded well back to 3440' and set 3 Sx. cement with dump bailer. Pulled 4 1/2" casing

and squeezed well initially with 5 sacks hulls and 20 sacks gel and followed with 100

Sx. cement from 800' to 475' then 7 sacks gel from 475' to 195' and followed with 20

Sx. cement from 195' to 130' then 3 sacks gel from 130' to 30' and finally 10 Sx.

cement from 30' to bottom of cellar. Maximum pump-in pressure-400#. FSIP--100#.

Recovered 997'--4 1/2" casing. (Mudding and cementing operations by Globe Cementing).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichole  
Well Plugging Supervisor

DATE 8/5/69

INV. NO. 249-W