

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

15-065-20564-00-00

SEP 10 1973
12-10-1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Murfin Drilling Company,

Complete Address 617 Union Center, Wichita, Kansas.

Lease Name Grecian Well No. 1

Location E/2-SW-NE Sec. 17 Twp. 10 Rge. (E) (W)21

County Graham Total Depth 3897'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling,

Address Box #176, Chase, Kansas. License No. 683

Operation Completed: Hour 11:00 AM Day 6 Month 9 Year 1973

The above well was plugged as follows:

177'--8 5/8" Surface casing, cement circulated with 135 Sx.

3893'--5 1/2" Production casing cemented on bottom with 150 Sx. Well Plugged back to 3826'. No perforations indicated.

Checked fluid level @ 3600'. Built wood & rock bridge @ 3600', sanded back to 3550'

and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing (2900') and squeezed well

initially with 5 Sx. hulls and 13 sacks gel and followed with 110 Cu. Ft. cement from

925' to 600' then 10 sacks gel from 600' to 200' and followed with 30 Cu. Ft. cement

from 200' to 125' then 2 sacks gel from 125' to 45' and finally 10 Cu. Ft. cement from

45' to bottom of cellar. Maximum pump-in pressure-400#. Final shut-in pressure-100#.

(Mudding and cementing operations performed by Allied Cementing, Inc.).

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: K. L. Nichols
Well Plugging Supervisor

DATE 9-10-73

INV. NO. 7894-W