



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
500 East Murdock, Wichita, Kansas


15-163-00474-00-00

Company- DON PRATT OIL CO.  
Farm- Kaster No. 1

SEC. 26 T. 10 R. 16W  
SW SW SW

Total Depth. 3647  
Comm. 2-26-52 Comp. 3-9-52  
Shot or Treated.  
Contractor. Sauvage & Dunn Drlg.  
Issued. 4-5-52

County Rooks KANSAS



Elevation. 2033 D.F.

Production. Dry

Figures Indicate Bottom of Formations.

cellar	5
shale & lime	135
shale	505
sand & shale	580
rod bed	695
sand	780
red bed, shale & shells	1140
red bed	1208
anhyd.	1250
red bed, shale & shells	1480
shale & shells	1550
salt & shale	1705
shale & shells	1800
shale & lime shells	1845
lime & shale	1990
lime & shale	2435
shale & shells	2875
shale & lime	3116
limed shale	3170
lime & shale	3285
lime	3330 ?
lime & shale	3330 ?
lime	3390
lime	3577
Congl.	3602
arb.	3647 RFD
Total Depth	

Tops: Meas. d. f.	
Cimarron anhyd.	1208 (drillor & Sch.)
Heobner shale black	3185
Toronto lime	3203 - 3219
Lansing-K.C.	3227
Base K.C.	3497
Warmaton	3497
Sooy Congl.	3554
Weathered Simpson	3579
arb. dolo.	3602

No shows in Wopeka lime  
No shows in Toronto

3298-3302 Partly xylm lime very spotted  
slight por. tr. dead stain  
3305-3308 some finely oolitic lime +  
slight to fair por. no show  
3322-3331 partly oolitic lime-spotted  
good por. w/show of free oil, fair odor.  
Spotted staining in dry sample  
D.S.T. 3322-3330 open 45 mins. filled 145'  
salt wtr. BHP 970# PSI.  
3359-3363 scattered pieces finely oolitic  
lime-spotted fair por. spotted staining.  
3438-3440 dense lime, tr drk stain.  
arb. dolo. spotted slight to good por, wtr.  
with no show of oil

RECEIVED  
THE CORPORATION COMMISSION  
MAY 22 1952  
CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING  
FILE SEC 26 T 10 R 16W  
BOOK PAGE 1 LINE 14