

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERRY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-163-22,047-00-00

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE NAME Nelson #1

WELL NUMBER #1

SPOT LOCATION SW NE SW

SEC. 27 TWP. 10 RGE. 16 (E) OR (W)

COUNTY Rooks

DATE WELL COMPLETED _____

PLUGGING COMMENCED 11-14-83

PLUGGING COMPLETED 11-14-83

LEASE OPERATOR Raymond Oil Company, Inc.

ADDRESS One Main Place Suite 900, Wichita, Ks. 67202

PHONE # (316) 267-4214 OPERATORS LICENSE NO. 5046

CHARACTER OF WELL Oil
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Hays, Kansas

IS ACC-1 FILED? Yes IF NOT, IS WELL LOG ATTACHED? _____

PRODUCING FORMATION _____ DEPTH TO TOP _____ BOTTOM _____ T.D. 3680'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS _____ CASING RECORD _____

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	248'	none
				5-1/2"	3678'	none

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

Mixed 50 sks cement with 3 sks hulls, 16 sks gel, 1/2 sk hulls, 25 sks cement, 6sks gel, 1/2 sk hulls, released plug and displaced with 80 sks cement. Max. Press 800#. Plugging Complete.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Raymond Oil Company, Inc. LICENSE NO. 5046
ADDRESS One Main Place Suite 900, Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Rice, SS.

W.R. Schoenhofer (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) W.R. Schoenhofer

(ADDRESS) P.O. Box 167 Lyons, Kansas 67554

SUBSCRIBED AND SWORN TO BEFORE ME THIS 17 DAY OF November, 19 83

Irene Hoover
NOTARY PUBLIC



MY COMMISSION EXPIRES: _____

RECEIVED
STATE CORPORATION COMMISSION
NOV 21 1983
11-21-1983
CONSERVATION DIVISION
Wichita, Kansas

FORM CP-4
REVISED 06-83

DRILLERS' WELL LOG

DATE COMMENCED: June 23, 1983
 DATE COMPLETED: June 30, 1983

Raymond Oil Co., Inc.
 NELSON #1
 SW NE SW
 Sec. 27, T10S, R16W
 Rooks County, Ks.

ELEVATION: 2078 K.B.

0 - 1269' Surface Soil, Post Rock, Shale
 1269 - 1309' Anhydrite
 1309 - 3290' Lime & Shale
 3290 - 3544' Lime
 3544 - 3680' Shale, Lime, Chert, Sand
 3680' RTD

FORMATION DATA

Anhydrite	1269'
Topeka	3011'
King Hill	3118'
Queen Hill	3176'
Heebner	3248'
Toronto	3266'
Lansing	3290'
Base K.C.	3544'
Marmaton	3567'
Conglomerate	3624'
RTD	3680'

Surface Pipe: Set new 8-5/8", 20#
 pipe @248' w/150 sacks 60/40 pozmix
 2% gel 3% cc.

Production Pipe: Set new 5 1/2", 14#
 @3678' w/250 sacks 50/50 pozmix
 and 150 sacks 60/40 pozmix, 7 1/2%
 salt.

A F F I D A V I T

STATE OF KANSAS
 COUNTY OF BARTON) ss

Ervin Neighbors of lawful age, does swear and state that the facts and
 statements herein re true and correct to the best of his knowledge.

Ervin Neighbors

Subscribed and sworn to before me this 7 day of July 1983.

My Comm. Expires:

4-29-86

L. Douglas M. Hague
 Notary Public

RECEIVED
 STATE CORPORATION COMMISSION
 OCT 5 1983
 10-05-1983
 CONSERVATION DIVISION
 Wichita, Kansas