

3-8

6 031509

065-20,811-00-00

API NUMBER 15-

NE NW NW, SEC. 31, T 9 S, R 24 W/Ex

4950 feet from S section line

4290 feet from E section line

Lease Name Riedel Well # 2

County Graham 133.90

Well Total Depth 4120 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 224

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5145

Operator: Dreiling Oil Inc.

Name & Address: Box 1000

Victoria, Ks. 67671

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement Co. License Number

Address Russell, Ks.

Company to plug at: Hour: AM Day: 8 Month: Mar Year: 19 91

Plugging proposal received from Ivan Edsall

(company name) Dreiling Oil (phone)

were: 8 5/8 set at 224 w/200 sks-cwc. 4 1/2 casing set at 4112 w/150 sks.

PBTD 4083 Perfs 4063 - 09. Order 350 sks 65/35 poz 10% gel

500 lbs. hulls. Shots at 2200 anhy 1340 Kiowa. Ran wireline to perfs.

Hole open.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:45AM Day: 8 Month: Mar Year: 19 91

ACTUAL PLUGGING REPORT Sq 4 1/2 casing w/250 sks cement blend w/500 lbs.

hulls mixed into max psi 700 lbs. Close in posi 300 lbs. Sq 8 5/8 w/100 sks cement blend to max psi 300 lbs. Close in psi 150 lbs. Plug complete.

RECEIVED STATE CORPORATION COMMISSION 04-04-1991 APR 04 1991 CONSERVATION DIVISION Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

I (did) ~~did not~~ observe this plugging.

DATE 4-11-91

INV. NO. 31472

Signed Carl Goodrow (TECHNICIAN) Carl Goodrow