

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 065- 21967-0000

SW, Sec. 36, T 9 S, R 24 W/4

1650 feet from #1/S section line

330 feet from W/4 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5430

Lease Name Sproull Well # 1

Operator: Energy Three Inc.  
Name & Address: Box 1505  
Great Bend Ks.

County Graham

Well Total Depth 4060 feet 131.95

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 284

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Big Three Drllg License Number 5836

Address Box 52 Graham Ks.

Company to plug at: Hour: 7:30 PM Day: 21 Month: 4 Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Stan Lovelady.

(company name) Big Three Drllg. (phone) 913 6375487

were: order 195 3x cement 50/50 poz mix 6% gel. 3% cat. cl.

1 5x hulls 1 8 5/8 plug 1 5x flow seal

Heavy mud between all plugs.

Pump cement down drill pipe.

Elev- 2455 Anhydrite 2074-2110 Arbuckle. No Dakota 1525

Signed Dale F. Battagor (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 4:30 AM Day: 22 Month: 4 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 2080 for 30 mi.

25 5x @ 2080

100 5x @ 1230 mixed w/ 1 5x flow seal

40 5x @ 320, 1 5x hulls pushed plug to 40'

10 5x @ 40

10 5x in Rat hole

10 5x in mouse hole

Remarks:

Cementing Co. Sun.

RECEIVED STATE CORPORATION COMMISSION  
APR 30 1984  
04-30-1984  
CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed Dale F. Battagor (TECHNICIAN)

INVOICED

DATE 4-30-84

INV. NO. 1297