

4-071020

11-27

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-065-22,700-00-00

NW SW NW /4 SEC. 36, 09 S, 24 W  
3630 feet from S section line  
4950 feet from E section line

Operator license# 5655 Lease Benson well # 1

Operator: Staab Oil Company County Graham

Address: Hays, Kansas 67601 Well total depth 4060 feet  
Francis Staab Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 262 feet

131.95

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Shields Drilling, Inc. License#           

Address: Russell, Kansas 67665

Company to plug at: Hour: A.M. Day: 27 Month: November Year: 92

Plugging proposal received from: Burt Berry

Company: Shields Drilling, Inc. Phone: 913-625-5013

Were: 8 5/8" 262' S.P. cwc. w/165 sx. 60/40 pozmix - 2% gel. - 3% cc.  
By B.J. Services. K.C. well - Elv. 2476' - Anhy. 2097' - No circulation  
problems. Mud condition 41 vis. - 8.7 Weight - 12.0 water loss.  
Proposal 200 sx. 60/40 pozmix - 6% gel. - 1 sx. flocele. Spot and  
displace cement thru drill stem, circulate hole, heavy mud between all  
plugs. 25 sx. @ 2100' - 100 sx. w/1 sack flocele @ 1300' - 40 sx. @  
310' - 10 sx. @ 40'. 15 sx. in rathole (circulate) 10 sx. in mousehole  
(circulate)

Plugging Proposal Received by: Marion J. Schmidt  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 10:00A.M., Day: 27, Month: November, Year: 92

Actual plugging report: Shields Drilling, Inc. order 200 sx. 60/40  
pozmix - 6% gel. - 1 sx. flocele. Circulate hole. Spotted and displaced  
all cement thru drill stem.  
1st. plug @ 2100' w/25 sx. cement.  
2nd. plug @ 1300' w/100 sx. cement with 1 sack flocele.  
3rd. plug @ 310' w/40 sx. cement.  
4th. plug @ 40' w/10 sx. cement.  
15 sx. in rathole (circulate) 10 sx. in mousehole (circulate)

Remarks: By Allied Cement.  
Condition of casing(in hole):GOOD  BAD  Anhy.plug:YES  NO   
Bottom plug(in place):YES , CALC , NO  Dakota plug:YES , NO   
Plugged through TUBING , CASING . Elevation: 2476 GL

RECEIVED  
STATE CORPORATION COMMISSION  
12-14-1992  
DEC 14 1992

I did  / did not  observe the plugging. Marion J. Schmidt

DATE 1-4-93  
INV. NO. 37084

#D (agent)