

6010163

API NUMBER 15-065-22007-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SW, SEC. 12, T. 9 S, R. 25 W/4  
1650 feet from ~~S/S~~ section line

990 feet from W/4 section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 8759

Lease Name Schamberger Well # 1

Operator: Mack Energy

County Graham

Name & Address Box 400

Well Total Depth 4130 134.23 feet

Duncan Okla 73533 Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1345 / 325

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well (D&A)

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Rains & Williamson License Number 5146

Address 220 W. Douglas Wichita KS.

Company to plug at: Hour: 6 PM Day: 6 Month: 7 Year: 19 84

Plugging proposal received from Mike Godfrey

(company name) Rains & Williamson (phone) 913-735-2215

were: order 170 sx. cement 50/50 permix 690 gal. 390 c.c.

1 sx hulls 1.8 5/8 plug

Heavy mud between all plugs

Pump cement down drill pipe

Elev. 2521 Anhydrite 2238-74 Arbuckle 4105

Dakota 1500 Plugging Proposal Received by Dale F. Balthazor  
(TECHNICIAN)

1021-1320

Plugging Operations attended by Agent?: All \_\_\_\_\_ (Part) \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12 AM Day: 7 Month: 7 Year: 19 84

ACTUAL PLUGGING REPORT circulated @ 4105 for 30 mi.

25 SX @ 4105

25 SX @ 2250

100 SX @ 1345 - Dumped 1-sx. hulls, pushed plug to 40'

10 SX @ 40

10 SX in Rat Hole

Remarks: Cementing w. Halliburton

(If additional description is necessary, use BACK of this form.)

INV. NO. 2618  
7-7

RECEIVED  
STATE CORPORATION COMMISSION  
Wichita, Kansas  
7-16-84  
JUL 16 1984

Signed Dale F. Balthazor  
(TECHNICIAN)

July 13  
5