

4-041345

12-14

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-065-22,657-00-00

SE SE NW /4 SEC. 15, 09 S, 25 W
3080 feet from S section line
3080 feet from E section line

Operator license# 6569

Lease Waggoner well # 1

Operator: Carmen Schmitt, Inc.

County Graham

Address: P.O. Box 47
Great Bend, Kansas 67530

Well total depth 4150 feet 134.84
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 212 feet
140 sx cmt.

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Duke Drilling Company License# 5929

Address: _____

Company to plug at: Hour: _____ Day: 14 Month: December Year: 91

Plugging proposal received from: Jay Schneider

Company: Duke Drilling Company Phone: _____

Were: Ordered 215 sx. 60/40 pozmix - 6% gel. with 1/4# flocele.
Spot all plugs through drill pipe and displace all cement plugs with
heavy mud.

Plugging Proposal Received by: Dennis Hamel

Plugging operations attended by agent? All[], Part[], None[]

Completed: Hour: 1:15P.M., Day: 14, Month: December, Year: 91

Actual plugging report: _____

Spot 25 sx. @ 2280'.

Spot 100 sx. @ 1380'.

Spot 40 sx. @ 260'.

Spot 10 sx. @ 40'.

15 sx. in Rathole.

RECEIVED
STATE CORPORATION COMMISSION

DEC 26 1991
12-26-91
Wichita

Remarks: Elevation: 2578'.

I did / did not observe the plugging.

Dennis L. Hamel

DATE 12-30-91

INV. NO. 34194

12-14

R.L.S.

(agent)

Form CP-2/3