

9-14 F-005-00193-00-01

031166

6

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1968

C NW SE, SEC. 21, T 9 S, R 25 W/E

1980 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5016

Lease Name Dreiling Well # 2

Operator: Energy Prod Inc County Graham 132.21

Name & Address 6121 E. Central Wichita, Ks. 67208

Well Total Depth 4068 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 233

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement Co. License Number

Address Russell, Ks.

Company to plug at: Hour: AM Day: 14 Month: Sept Year: 19 88

Plugging proposal received from Leroy Cline

(company name) Energy Prod Inc. (phone)

were: 8 5/8" set at 233' w/150 sks cwc. 4 1/2" set at 4065' w/500 sks cwc. O.H.

4065' - 4068'. Order 200 sks 60/40 Poz 8% Gel 500# Hulls. Allied Cement Co. Emphasis

Water Truck.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:25AM Day: 14 Month: Sept Year: 19 88

ACTUAL PLUGGING REPORT Squeeze 4 1/2" casing w/200 sks cement w/500# Hulls to

max psi 300#. Close in psi 150# Plug complete. Annulus full of cement.

Remarks:

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-24-88

Signed Carl Goodrow (TECHNICIAN) Carl Goodrow

INV. NO. 22673