

To: 6 031564  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

7-6  
API NUMBER 15- 179-21,010-00-00 217 R

C/ N/2 NE, SEC. 30, T 9 S, R 26 W/E  
4620 feet from S section line  
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5663  
Operator: Hess Oil Company  
Name & Address 412 E. Douglas #1  
Wichita, Kansas 67202

Lease Name Maxwell Well # 1  
County Sheridan 131,30  
Well Total Depth 4040' feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 212

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A x  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mallard Drilling License Number 4958  
Address McPherson, Kansas

Company to plug at: Hour: \_\_\_\_\_ P.M. Day: 6 Month: 7 Year: 19 91

Plugging proposal received from Office (Bryson)  
(company name) Mallard Drilling (phone) \_\_\_\_\_

were: 8 5/8 set @ 212' cwc. 140 sx. circ. hole with no less than 36 vis. mud with no  
loss or gain of fluid. Balance plugs with mud. Order 200 sx. 60/40 poz.  
6% zel. 3% cc. Allied Cement Company.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 11:45 P.M. Day: 6 Month: 7 Year: 19 91

ACTUAL PLUGGING REPORT Spot plugs with drill pipe with 25 sx. @ 2250'.  
100 sx. @ 1300' Halls.  
40 sx. @ 260'.  
10 sx. @ 40'. w/W.P.  
circ. 15 sx. in Rathole.  
circ. 10 sx. in Mousehole.

Remarks: Anhy. 2219-59 - Elv. 2558.  
(if additional description is necessary, use BACK of this form.)

XXXXX (if not) observe this plugging.

**INVOICED**  
DATE 8-28-91  
INV. NO. 32878

*J. S.*

Signed Carl Goodrow  
(TECHNICIAN)

RECEIVED  
08-21-1991  
AUG 21 1991  
CONSERVATION DIVISION  
Wichita, Kansas  
FORM CP-2/3  
Rev. 01-84