

4 050083

173  
R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 179-20,983-00-00  
NE NE NE, SEC. 4, T 9, S, R 27 WXE

4950 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9860

Lease Name Sharon Well # 1

Operator: Castle Resources

County Sheridan 129.67

Name & Address: Route 1, Box 90

Well Total Depth 3990 feet

Hays, Kansas 67601

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 246

Abandoned Oil Well Gas Well Input Well SWD Well D&A xx

Other well as hereinafter indicated

Plugging Contractor Emphasis Oil Operations License Number

Address

Company to plug at: Hour: AM Day: 4 Month: Jan Year: 19 91

Plugging proposal received from John Collins

(company name) (phone)

were: Order 190 sks 60/40 poz 6% gel 1/4 lb f.c. per sk w/8 5/8 wiper plug.

Spot all plugs through drill pipe w/heavy mud between all plugs.

Plugging Proposal Received by (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None xx

Operations Completed: Hour: 4:00 AM Day: 4 Month: Jan Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 2220 w/25 sks

2nd plug at 1350 w/100 sks

3rd plug at 300 w/40 sks

4th plug at 40 w/10 sks and 8 5/8 wiper plug: RECEIVED STATE CORPORATION COMMISSION

Rathole 15 sks

Cemented by Halliburton

JAN 28 1991

01-28-1991

Remarks: Elevation 2594 Anhydrite 2205-35 No Arb.

(If additional description is necessary, use BACK of this form.)

INVOICED

I (xxx / did not) observe this plugging.

DATE 2-11-91

INV. NO. 30645

Signed Marvin Miller (TECHNICIAN)

Gabe S

Marvin Miller