

6090022

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-179-20, 708-00-00

SE 1/4 SEC. 5, T 9 S, R 27 W 1/2

1650 FEET FROM N/S SECTION LINE

2310 FEET FROM N/E SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 6066

LEASE NAME Kennedy WELL # 1

OPERATOR: Stylene Petroleum
NAME & ADDRESS P.O. Box 70
Ways, Ks. 67601

COUNTY Meriden

WELL TOTAL DEPTH 4100 ^{133.25} FEET

CONDUCTOR PIPE: SIZE - FEET -

SURFACE CASING: SIZE 8 5/8 FEET 240

ABANDONED OIL WELL _____ GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR Big Springs Drilling LICENSE NUMBER 5381

ADDRESS P.O. Box 8287 Mungen Station Wichita, Ks. 67208

COMPANY TO PLUG AT: HOUR: 6:00 PM DAY: 8 MONTH: November YEAR: 19 83

PLUGGING PROPOSAL RECEIVED FROM Steve Basin

(COMPANY NAME) Big Springs Drilling (PHONE) 316-681-1732

WERE: Order 180 sha. 50/50 permit, 6 7/8" gel, 3 7/8" Cal. Cl. + 8 5/8" wire plug, spot all plugs w/ drill pipe w/ heavy mud between all plugs.

PLUGGING PROPOSAL RECEIVED BY Edwin A. Schumacher (TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART _____ NONE

OPERATIONS COMPLETED: HOUR: 6:00 PM DAY: 8 MONTH: November YEAR: 19 83

ACTUAL PLUGGING REPORT 1st plug 2300' w/ 20 sha. cmt.
2nd plug 1413' w/ 100 sha. cmt. 1 sh. cello Flash
3rd plug 290' w/ 40 sha. cmt.
4th plug 40' solid bridge 1 sh. bulls 10 sha. cmt.
10 sha. cmt. rat hole

REMARKS: Elevation - 2663'
Anhydrite - 2297' (Sun Cementing)
Arbuckle - no

I (DID / DID NOT) OBSERVE THIS PLUGGING.

SIGNED Edwin A. Schumacher (TECHNICIAN)

INVOICED

DATE 1-4-84

INV NO. 7294 W

RECEIVED
STATE CORPORATION COMMISSION
NOV 21 1983
11-21-1983
CONSERVATION DIVISION
Wichita, Kansas

FORM CP-273
8 REV. 6-83