

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-179-20, 701-00-00

TECHNICIAN'S PLUGGING REPORT

SW-NW-NE, Sec. 7, T 9 S, R 27 W E

2307 feet from NS section line

1980 feet from WE section line

Operator License # 7190

Lease Name ^{Ray 2nd} HAFFNER Well # 1

Operator: PETRO-TECHNOLOGY
Name & Address: BOX 4586
TOPEKA, KANSAS
66604

County SHERIDAN

Well Total Depth 4075 feet \$132.44

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 256

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor MURKIN DRILLING Co. License Number TAG # 607 6023

Address 617 UNION CENTER BLDG. WICHITA, Mo. 67202

Company to plug at: Hour: 12:00 PM Day: 26th Month: Oct Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO ALFRED AUGUSTINE

(company name) MURKIN DRILLING, Inc (phone) 316-267-3241

were:
8 5/8" - 256 FT SB. CUL #190 ^{SS} QUICK SET. (BY ALLIED OMT)
ORDER 190 ^{SS} 50/50 FORMIX 6% GEL-3% CA-CL. AND 8 5/8" PLUG
SPOT WITH DRILL STEM - TURN HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS.
NO AIRBUCKLE - NK WELLS

Signed *Alfred Augustine*
(TECHNICIAN)

Plugging Operations attended by Agent: All _____ Part _____ None

Operations Completed: Hour: 12:00 PM Day: 26th Month: Oct Year: 1983

ACTUAL PLUGGING REPORT

ORDERED 190 ^{SS} 50/50 FORMIX 6% GEL-3% CA-CL. AND 8 5/8" PLUG.
SPOTTED WITH DRILL STEM - TURNED HOLE OVER - HEAVY MUD BETWEEN ALL PLUGS.
1st Plug @ 2280 FT #20 ^{SS} OMT, 2nd Plug @ 1140 FT #100 ^{SS} OMT, ^{SS}
3rd Plug @ 270 FT #50 ^{SS} OMT, 4th Plug ^{SS} SAND BRIDGE HALLS-PLUG @ 40 FT #10 OMT, ^{SS}
10 ^{SS} IN RAT HOLE (CIRCULATE)

Remarks: _____

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED 11-2-83
DATE 11-2-83
INV. NO. 6024-0
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

Signed *Alfred Augustine*
(TECHNICIAN) 601