

6 070347

API NUMBER 15-179-20,805-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION SW-SE-SW, SEC. 10, T. 9 S, R 27 (W) #
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

330 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9883

Lease Name WHITE Well # 2

Operator: SHARON RESOURCES, INC.

County SHERIDAN 133.25

Name & Address: 7100 E. BELLEVUE ST.

Well Total Depth 4100 feet

201 ENGLEWOOD, CO.

Conductor Pipe: Size 0 feet

8011

Surface Casing: Size 8 5/8 feet 309 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated TAG # 604

Plugging Contractor MURFIN DRUG. INC. License Number 6033

Address WICHITA, KANSAS, 67202

Company to plug at: Hour: 11:00 PM Day: 2 ND Month: APRIL Year: 19 85

Plugging proposal received from LLYOD DELETT

(company name) MURFIN DRUG. INC. (phone) 303-595-9111

were: 8 5/8" 309 EI 50. CUC #/200 SK 60/ 40 Pozmix CA-CL - By Halliburton

ORDER 200 SK 50/50 Pozmix GEL - CA-CL - 2 SK CELLO FLAME AND 8 5/8" PLUG.

SPOT WITH DRILL STEM, RECONDITION HOLE (4 5/8") HEAVY MUD BETWEEN ALL PLUGS.

NO CIRCULATION PROBLEMS, MUD CONDITION Weight 9.6 - Visc 49. Chl 13000

FLV. 2668 - AMH. 2559,

Plugging Proposal Received by Maurice Schmidt
DDIC (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 11:15 PM Day: 2 ND Month: APRIL Year: 19 85

ACTUAL PLUGGING REPORT ORDERED 200 SK 50/50 Pozmix GEL - CA-CL - 2 SK CELLO FLAME AND 8 5/8" PLUG.

SPOTTED WITH DRILL STEM RECONDITION HOLE, HEAVY MUD BETWEEN ALL PLUGS.

1ST PLUG @ 2280 FT #/30 SK CNT, 2ND PLUG @ 1410 FT #/100 SK CNT + 1 SK CELLO FLAME.

3RD PLUG @ 320 FT #/50 SK CNT, 4TH PLUG SOLID BRIDGE HULL-PLUG @ 40 FT #/10 SK CNT.

10 SK CNT IN BAT HOLE (CIRCULATE) By Halliburton

RECEIVED STATE CORPORATION COMMISSION

APR 15 1985

04-15-1985

Remarks: _____
(If additional description is necessary, use BACK of this form. Wichita, Kansas)

INVOICED (if not) observe this plugging.

DATE 4-18-85

NO. 7773

Signed Maurice Schmidt
DDIC (TECHNICIAN) 4-12-85 mgg

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

Corrected
CARD MUST BE SIGNED
3-26-85

Starting Date: 03 27 85
month day year

API Number 15- 179-20,805-00-00
SW SE SW Sec 10 Twp 9 S, Rge 27
(location) East West

OPERATOR: License # 9883
Name Sharon Resources, Inc.
Address 7100 E. Belleview, St., 201
City/State/Zip Englewood, CO 80111
Contact Person Charles Davis
Phone 303-595-9111

* 330 Ft North from Southeast Corner of Section
* 3630 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 6033
Name Murfin Drilling Company
City/State Wichita, KS

Nearest lease or unit boundary line *330 feet.
County Sheridan
Lease Name White Well# 2
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Depth to Bottom of fresh water 200 feet
Lowest usable water formation Dakota
Depth to Bottom of usable water 1425 feet

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 4120 feet
Projected Formation at TD BKC
Expected Producing Formations LKC

Surface pipe by Alternate: 1 2
Surface pipe to be set 300 feet
Conductor pipe if any required N/A feet
Ground surface elevation 2663 feet MSL
This Authorization Expires 9-25-85
Approved By 3-25-85

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications. * was. 410 FSL 3530 FSL

Date 3-26-85 Signature of Operator or Agent *J. E. Goss* Title Ass't. Drilling Manager
Jack E. Goss, Agent for Operator Form C-1 4/84

RECEIVED
STATE CORPORATION COMMISSION
APR 15 1985
CONSERVATION DIVISION
Wichita, Kansas