

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-179-20,733-00-00

SW SW SW, Sec. 12, T 9 S, R 27 (W/E)

330 feet from N/S section line

330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6041

Lease Name Breeden Well # 11

Operator: Petroventures
Name & Address 4704 Harlon Suite 600
Denver, Colorado 80212

County Sheridan

Well Total Depth 4125 feet 13406

Conductor Pipe: Size feet

Surface Casing: Size 8^{5/8} feet 290 - 250 sks

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Dunn & Gardner License Number 9180

Address 200 West Douglas, Wichita, Ks. 67202

Company to plug at: Hour: PM Day: 29 Month: February Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Herb Boxberger

(company name) Dunn & Gardner (phone)

were: Order 180 50/50 pozmix 4% gel 3% cc 8^{5/8} plug. Jetts pitts cir hole with heavy

mud - displace 20 sks cement thru drill pipe ^{42300'} heavy mud to 1450' and displace 100 sks

cement thru drill pipe - heavy mud to 300' and displace 40 sks cement thru drill pipe -

heavy mud to 40' set cementing plug 1/2 sks hulls and 10 sks cement cementing to base
of celler - 10 sks in rat hole

By Sun Cementing

Signed Gilbert P. Leiker
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 4:30 PM Day: 1 Month: March Year: 1984

ACTUAL PLUGGING REPORT

1st plug @ 2300 w/20 sks

2nd plug @ 1450 w/100 sks

3rd plug @ 300 w/40 sks

4th plug @ 40 w/10 sks plug 1/2 hulls

10 sks in Rat Hole

Remarks:

RECEIVED
STATE CORPORATION COMMISSION

MAR 05 1984
03-05-1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (did / did not) observe this plugging.

Signed Gilbert P. Leiker
(TECHNICIAN)

INVOICED

DATE 3-12-84

INV. NO. 0683